

UNION COUNTY GOVERNMENT
SPIVA COVE ROAD
MATERIAL QUANTITIES AND COST ESTIMATE

Developer: Union County Government
Project: 25011UCGD
Location: Union County, Ga
Date: 10/5/2026

Item No.	GDOT Item Description	GDOT Item #	Quantity	Unit	Unit Price	Total Price	Notes
----------	-----------------------	-------------	----------	------	------------	-------------	-------

SITEWORK

1.0	Demo						
1.1	Removal of Existing Structure	540-1101	1.0	LS	\$	\$	
2.0	Permanent Bridge Structure						
2.1	80' X 14' Bridge with Concrete Abutment and Wingwall	500-3015	1.0	JOB	\$	\$	Approx. 22 CY of Concrete
2.2	Gr Aggr Base Crs, 8 Inch, incl Matl	219-3120	2025.0	SY	\$	\$	
2.3	1.5 in Asphalt 9.5 mm Superpave	402-3910	2025.0	SY	\$	\$	
2.4	2.5 in Asphalt 19 mm Superpave Base Course	402-4012	2025.0	SY	\$	\$	
2.5	Concrete Bridge Decking	500-3830	30.0	CY	\$	\$	
2.6	Riprap Scour Protection	603-1300	125.0	TONS	\$	\$	
					SUB-TOTAL =	\$	

EROSION CONTROL

3.0	Dam Area Vegetation & Structural Measures						
3.1	Silt Fence	171-0030	582.0	LF	\$	\$	Sd1-S
3.2	Temporary Vegetation	163-0232	0.3	AC	\$	\$	Ds1 & Ds2
3.3	Permanent Vegetation	700-6910	0.3	AC	\$	\$	Ds3
3.4	Construction Exit	163-0300	1.0	EA	\$	\$	Co
3.5	Hay Bale Check Dam	162-1300	5.0	EA	\$	\$	CD-HB
3.6	Erosion Control Testing	167-0100	1.0	JOB	\$	\$	NPDES Monitoring
					SUBTOTAL	\$	

MISCELLANEOUS

5.0	Construction General						
5.1	Mobilization	151-1000	1	JOB	\$	\$	(0 CY Cut / 240 CY Fill)
5.2	Grading Complete	210-0000	1	JOB	\$	\$	
					SUBTOTAL	\$	

CONSTRUCTION TOTALS

ESTIMATED SUBTOTAL \$ _____
ESTIMATED CONTINGENCIES (10%) \$ _____
TOTAL ESTIMATED CONSTRUCTION COST \$ _____

UNION COUNTY GOVERNMENT
SPIVA COVE ROAD
 MATERIAL QUANTITIES AND COST ESTIMATE

Developer: Union County Government
Project: 25011UCGD
Location: Union County, Ga
Date: 10/5/2026

Item No.	GDOT Item Description	GDOT Item #	Quantity	Unit	Unit Price	Total Price	Notes
----------	-----------------------	-------------	----------	------	------------	-------------	-------

GENERAL NOTES

Unit Price Descriptions		
Unit Abbreviation	Unit Description	Unit Type
LS	Lump Sum	Single Payment
AC	Acre	Area
CY	Cubic Yards	Volume
GLF	Gross Linear Feet	Length
LF	Linear Feet	Length
EA	Each	Number
SY	Square Yard	Area
TONS	Tons	Weight
JOB	Job	Single Payment
GL	Gallons	Volume