

**SECTION 01 11 00  
SUMMARY OF WORK**

**PART 1      GENERAL**

**1.1      SUMMARY**

**A.    Section includes the following:**

1.    Work Covered by Contract Documents.
2.    Work Phases.
3.    Materials and Work by Others.
4.    Work Under Other Contracts.
5.    Government-Furnished Materials.
6.    Contractor Use of Site.
7.    Public Use of Site.
8.    Occupancy Requirements for Buildings.
9.    Conduct of Operations.
10.   Work Restrictions.
11.   Special Construction Requirements.
12.   Soils Investigation Report.
13.   Additional Reports.

**1.2      WORK COVERED BY CONTRACT DOCUMENTS**

**A.    Project Location: Grand Canyon National Park, Arizona, in South Rim Village at South Rim Wastewater Treatment Plant (WWTP).**

**B.    The Work required in the base scope as described in Section 01 27 00, Definition of Contract Line Items, include the following scope as described herein but not limited to:**

1.    South Rim WWTP replacement to include the following:
  - a.    Site preparation, including tree protection, tree removal and grubbing of previously undisturbed areas outside of existing WWTP fence line.
  - b.    Relocation of existing on-site metal storage containers and existing storage sheds contents into temporary off-site storage containers.
  - c.    Temporary process facilities and relocations.
  - d.    New 0.65 million gallons per day (mgd) treatment processes constructed at the existing plant site including: headworks building, septage receiving station, process building, process tanks, equalization tank, reclaimed water tank, digester facility, drying beds, compost facility, odor control facility, plant drain pump station.
  - e.    New administration building, maintenance building, and covered storage.
  - f.    New emergency generator with integral fuel tank.

- g. Modifications to existing backwash holding pond to convert it to stormwater pond.
  - h. New site yard piping and site utilities.
  - i. Utility connections and tie-ins to existing influent sewer, effluent discharge pipeline, reclaimed water piping and potable water.
  - j. New site power and electrical.
  - k. New instrumentation and process control systems.
  - l. New site grading, landscaping and paving.
  - m. Site fencing.
  - n. Chemicals and consumables required for WWTP equipment testing, facility start-up and demonstration.
- 2. South Rim WWTP demolition of existing facilities, disposal of demo materials and site restoration to include the following:
    - a. Existing on-site temporary storage sheds.
    - b. Existing control building, pretreatment / digester building, aeration tanks and pipe gallery, secondary clarifiers, flow equalization tanks, drying beds, reclamation plant, backwash holding pond.
    - c. Yard piping, utilities and site electrical.
  - 3. South Rim WWTP new treatment facilities operation and maintenance for a 12-month period as described in Section 01 78 25, Operations and Maintenance Support Services.
  - 4. Improvement of existing two track access road from APS Substation located at the west terminus of Clinic Road to South Rim WWTP and construction of a road extension to new SR WWTP west access gate, to include the following:
    - a. Site preparation, including tree removal and grubbing of previously undisturbed areas along proposed road alignment.
    - b. Erosion control.
    - c. Environmental, cultural and archeological mitigation.
    - d. Installation of culvers.
    - e. Manhole adjustments.
    - f. Grading, installation of aggregate base and asphalt concrete pavement.
    - g. Site restoration, seeding/mulching.
- C. The optional work items as described in Section 01 27 00, Contract Line Items, include the following work:
- 1. Field services for testing passive radon gas mitigation systems in new buildings according to Section 31 21 13, Radon Mitigation – Option A.
  - 2. Install active radon gas mitigation system in new buildings, if based on testing it is determined necessary to reduce and maintain radon concentration, as specified in Section 31 21 13, Radon Mitigation, and shown on Drawings – Option B.

- D. Project will be constructed under a single prime Contract. Government will take Beneficial Occupancy of certain Project elements as they are completed, prior to Substantial Completion of the Work as a whole.
- E. Warranties on Contractor workmanship and materials, and Manufacturer/Supplier warranties on equipment and performance for period not less than 1 year from the date of Substantial Completion.

### 1.3 WORK PHASES

- A. The Work shall be conducted in three phases in the following order, with each phase substantially complete before beginning next phase, unless otherwise approved by the Contracting Officer. Refer to the Drawings for a visual representation of the construction areas, temporary facilities, demolition and phasing. Refer to Section 01 91 14, Equipment Testing and Facility Startup, for additional information on treatment facility startup sequence and requirements. Refer to Section 01 91 15, Total Building Commissioning, for additional information on building and building systems startup requirements. Additional steps and phasing will be required and it is the responsibility of the Contractor to develop a complete work sequencing approach which must be approved by the Contracting Officer.
- B. Access Road Improvements
  - 1. Construct minimum improvements to existing two track road needed to facilitate access for Contractor staff, and materials and equipment deliveries to the project site on a year-round basis during South Rim WWTP construction.
  - 2. Maintain access road for Contractor use during construction.
  - 3. Work should be substantially complete and ready for occupancy at time of Substantial Completion.
- C. South Rim WWTP Phase 1:
  - 1. Complete process relocations and install temporary facilities.
  - 2. Complete relocation of contents of temporary storage sheds to off-site temporary storage and demolition.
  - 3. Relocate existing metal storage containers.
  - 4. Remove trees, clear and grub site for new treatment facilities.
  - 5. Construct new liquid and solids wastewater treatment facilities in areas not currently occupied by existing treatment facilities, including headworks building, septage receiving station, process building, process tanks, reclaimed water tank, digester facility, drying beds, plant drain pump station.
  - 6. Construct administration building.
  - 7. Construct exterior covered storage adjacent to administration building.
  - 8. Install new primary power connection and install emergency generator.
  - 9. Complete site grading, paving, and fencing.
  - 10. Complete startup testing and commissioning of constructed buildings and wastewater treatment facilities, complete tie-ins, demonstrate performance.

11. Obtain acceptance of Phase 1 work by the Government.
12. Assume 12-month operation and maintenance of new treatment facilities. Refer to Section 01 78 25 Operation and Maintenance Support Services.
13. Transition operation from existing wastewater treatment facilities to new treatment facilities.
14. Work within the South Rim WWTP Site shall be performed to minimize impacts to the operation and maintenance of the existing treatment facilities. Completion of this phase is required before proceeding with Phase 2.

D. South Rim WWTP Phase 2:

1. Cleanout wastewater, sludges, and any remaining process fluids and residues from existing treatment facilities and basins.
2. Decommission and demolish existing buildings and treatment facilities, install structural backfill and restore area to grade.

E. South Rim WWTP Phase 3:

1. Construct maintenance building, adjacent covered storage, and parking area in location of previously demolished drying beds.
2. Construct compost facility in location of previously demolished clarifiers and control building.
3. Construct odor control facility.
4. Complete stormwater pond conversion.
5. Complete remaining site restoration, paving and landscaping.
6. Complete startup testing, commissioning and integration of facilities constructed in this phase. Demonstrate performance.
7. Obtain acceptance of Phase 3 work by the Government.
8. The remaining Work shall be substantially complete and ready for occupancy at time of Substantial Completion.

#### 1.4 MATERIALS AND WORK BY OTHERS

A. Work depicted in the Contract Documents will be procured by Government and performed by others. The work will be conducted simultaneously with work under this Contract and require Contractor coordination to ensure efficient and timely completion of Work.

1. South Rim WWTP PLC and SCADA Integration: A separate contract will be awarded to Process Control System Integrator (SI) to perform the following work as part of and in support of South Rim WWTP Replacement project:
  - a. Programming and configuration of the main Plant PLCs and SCADA system.
  - b. Acquiring and providing the necessary PLC and SCADA software licenses for the South Rim WWTP.

- c. Conducting software integration workshops to finalize the control narratives for programming the main Plant PLCs and SCADA system.
- d. Participating and contributing to the software integration workshops with the packaged system vendors to finalize the programming requirements for the vendor systems and the main Plant PLCs.
- e. Developing submittals for the draft and final control narratives prior to programming the main Plant PLCs and SCADA system.
- f. Testing (Factory Acceptance, Field testing and commissioning) of the main plant PLCs and SCADA software.
- g. Coordinating the software integration workshops and submittals with the Park Service and the General Contractor for this Project.
- h. Provide training for the main plant PLCs and SCADA programs.
- i. Provide warranty and support for the main plant PLCs and SCADA software and hardware.
- j. Develop O&Ms and loop (interconnect) drawings for the plant control system.

2. Arizona Public Service (APS). Power utility connection

- a. APS will provide new primary feeder to the SR WWTP CT Cabinet in a trench and conduit provided by Contractor.
- b. APS will install Current Transformer (CT) meter in the allocated section of the switchboard.
- c. Contractor Coordination: Contractor shall submit product information to Contracting Officer for the CT Cabinet enclosure for review by APS prior to ordering materials and coordinate in a timely fashion with APS to allow for design and installation of primary feeder.

1.5 WORK UNDER OTHER CONTRACTS

- A. General: Cooperate with separate contractors so work on those contracts may be carried out smoothly, without interfering with or delaying work under this Contract. Coordinate Work of this Contract with work performed under separate contracts.
- B. Existing NPS Operations: Contractors work area is adjacent to and within existing wastewater treatment facility. Contractor shall coordinate construction activities with NPS Operations as to not interfere with plant operations. NPS Operations will have final authority to stop construction work during operational emergencies.

- C. Preceding Work: Government has awarded separate contract(s) for the following construction operations at or near the Project Site. Those operations are scheduled to be substantially complete before work under this Contract begins.
1. GRCA 190083 Replace Transcanyon Waterline and Improve Potable Water Systems:
    - a. A separate contract has been awarded to improve various potable water treatment and conveyance facilities throughout the Park. The improvements are outside of South Rim WWTP Project Site and include:
      - 1) Construct new South Rim Water Treatment Plant (WTP) with a production capacity of 1.8 million gallons per day (mgd) on South Rim.
      - 2) Construct new Phantom Ranch WTP with production capacity of 1.0 mgd.
      - 3) Rehabilitate existing Transcanyon Waterline (TCWL).
      - 4) Rehabilitate existing Bright Angel Water Supply Pipeline.
      - 5) Replace existing Havasupai Gardens potable water supply.
      - 6) Construct Indian Garden Pump Station.
- D. Concurrent Work: Government has awarded separate contract(s) for the following construction operations at or near Project Site. Those operations will be conducted simultaneously with work under this Contract.
1. GRCA 250440 Shuttle Bus Maintenance Facility:
    - a. A separate contract has been awarded to construct a new bus maintenance facility in the general vicinity of the Contract Support Facilities Area 2.b as described below. Expect common use of the access road to Area 2.b.
  2. GRCA 318719 North Rim Utilities:
    - a. Construction of new wastewater and water treatment plants, water and sewer and water pipelines on the North Rim of Grand Canyon. Contract will require helicopter activity from the South Rim helicopter base located to southeast of project site and access via the Contractor Support Facility Area 2.b as described below.
- E. Future Work: Government will award separate contract(s) for the following additional work to be performed at Site after Substantial Completion. Completion of that work will depend on successful completion of preparatory work under this Contract.
1. None.

## 1.6 GOVERNMENT-FURNISHED MATERIALS

### A. In case of Government-furnished materials:

1. Government will arrange and pay for delivery of Government-furnished items according to Contractor's Construction Schedule.
2. Contractor is responsible for initial inspection, receiving, unloading, and handling Government-furnished items at Project Site.
3. Government will inspect delivered items for damage after delivery. Contractor shall be present for and assist in Government's inspection.
4. Government will arrange for replacement if Government-furnished items are damaged, defective, or missing.
5. Contractor is responsible for protecting Government-furnished items from damage during storage and handling, including damage from exposure to the elements.
6. If Government-furnished items are damaged as a result of Contractor's operations, Contractor shall repair or replace them.
7. Contractor shall install and otherwise incorporate Government-furnished items into Work.

### B. Government-Furnished Materials:

1. Hydroseed, as shown on the Landscape Drawings.
2. Landscape vegetation, as shown on the Landscape Drawings.

## 1.7 CONTRACTOR USE OF SITE

### A. General: Contractor shall have limited use of site for construction operations. Limit use of premises to work in areas indicated on the Drawings. Do not disturb portions of Project Site beyond areas in which the Work is indicated.

1. Limits: Confine constructions operations to areas of existing South Rim WWTP and within Limits of Construction noted on the Drawings. Utilize areas made available for Contractor use during construction in accordance with Section 01 50 00, Temporary Facilities and Controls.
2. Limit impact on existing South Rim WWTP operations. The existing South Rim WWTP shall remain online and fully operational at all times with unrestricted access for NPS operations staff to existing treatment facilities during construction until transition from the existing treatment facilities to the newly constructed facilities. Once treatment operations transition to the Replacement South Rim WWTP, new treatment facilities shall remain online and fully operational at all times with unrestricted access for NPS operations staff.
3. Limit site disturbance, including earthwork and clearing of vegetation, to areas indicated on Drawings. Confine constructions operations limits of disturbance shown within the Civil Drawings. Coordinate with requirements of Section 31 10 00, Site Clearing.

- B. Contractor Support Facilities: Areas provided within the park, outside of the project site, for limited contractor use during construction. Coordinate use of Contractor Support Facilities with Contracting Officer.
1. The Contractor shall use the Contractor Support Facilities to the maximum extent practical based on the following Project objectives:
    - a. Minimize traffic impacts associated with Contractor staff entering/exiting the Park.
    - b. Minimize traffic on roads accessible to the public.
    - c. Allow for continuity of staff, NPS access to Contractor staff, and emergency preparedness during construction.
    - d. Mitigate inherent safety issues associated with the remote work site(s) and commuting from remote locations.
  2. The following Contractor Support Facilities are to be used and maintained by the Contractor:
    - a. Contractor Construction Operations and Staging:
      - 1) An approximate less than 1-acre area located southeast of and adjacent to South Rim WWTP fenceline bordered by the existing Nursery fenceline and two track Power Line Road, as shown on the Drawings.
      - 2) Contractor shall provide fencing and access gates and maintain locked gates when not in use and provide key access to CMR staff.
      - 3) Contractor shall provide 12 parking spots with unrestricted access that are safely accessible on year round basis and solely for the benefit of NPS Operations staff.
      - 4) Contractor shall provide and install temporary storage containers accessible to and for the sole use of NPS Operations staff throughout duration of construction, as shown on the Drawings.
    - b. Contractor RV Trailer Parking: Existing 20 construction RV trailer pad site(s) and adjacent approximate 1-1/2 acre graded area located west of FMD facility are provided for Contractor use.
      - 1) Contractor shall be responsible for maintaining RV trailer area and the cost of utilities.
    - c. Contractor Laydown Area:
      - 1) An approximate 8-acre off-site area located within park boundary consisting of crushed aggregate surfacing for contractor personnel and construction vehicle parking, contractor trailers, material storage, equipment maintenance, and similar construction support operations.

- 2) Fencing and access gates are provided for the contractor trailer and laydown site area. Contractor shall maintain locked gates when not in use and provide key access to CMR staff.
  - d. Contractor Stockpiling and Spoils Storage Area: An approximate 1.5-acre area for storage and management of excavated spoils from project site located off-site within park boundary. No construction materials or equipment storage other than equipment for the management of spoils is permitted. Contractor to provide stormwater management.
  - e. Approximately 1-mile of two track Power Line Road from APS Substation, located at the west terminus of Clinic Road, to the existing SR WWTP. Contractor plans for temporary road improvements to facilitate year-round construction traffic access to the project site shall be within the limits of construction as shown on the Drawings and be submitted for Contracting Officer approval. Contractor shall maintain road for year-round access for Contractor staff, and equipment and materials delivery to project site throughout duration of construction. Road shall be accessible to NPS staff for access to SR WWTP and APS power utility for maintenance of power lines.
- C. Storage of Materials: Confine storage of materials to the staging and storages areas shown on the Civil Drawings in the Contract Documents. Consult with Contracting Officer approval of final locations for material and equipment storage.
- D. Parking: Confine parking to the staging areas as shown on the Civil Drawings in the Contract Documents.
- E. Stockpiling: Confine stockpiling to staging areas or within the Limits of Construction as shown on the Drawings.
- F. Preservation of Natural Features:
1. Prevent damage to natural surroundings. Restore damaged areas, repairing or replacing damaged trees and plants, at no additional expense to the Government.
  2. Provide temporary barriers to protect existing trees and plants and root zones.
  3. Do not remove, injure, or destroy trees or other plants without prior approval. Consult with Contracting Officer (CO) and remove agreed-on roots and branches that interfere with construction.
  4. Do not fasten ropes, cables, or guys to existing trees.
  5. Carefully supervise excavating, grading, filling, and other construction operations near trees to prevent damage.

- G. Driveways and Entrances: Keep driveways and entrances serving premises clear and available to Government employees, and emergency vehicles at all times. Do not use for parking or storage of materials.
1. Consult with NPS and Contracting Officer (CO) to schedule deliveries to minimize impact on visitors.
  2. Deliveries shall not impact access roads, driveways and entrances in the vicinity of South Rim WWTP used by WWTP Operations, septage haulers, Grand Canyon Kennel visitors and staff, and Grand Canyon Nursery staff.
  3. Schedule deliveries to minimize use of South Rim WWTP driveways and entrances.
  4. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site. Materials shall be stored, fabricated, and transported from the Contractor's storage area within the Contractor Support Facilities site.
- H. Construction Camp: Establishment of a camp within park will not be permitted except areas designated as Contractor Support Facilities listed in this section.
- I. Hauling Restrictions: Comply with legal load restrictions in hauling of materials. Load restrictions on park roads are identical to state load restrictions with such additional regulations as may be imposed by the Park Superintendent. Information regarding rules and regulations for vehicular traffic on park roads may be obtained from the Office of the Park Superintendent. A special permit will not relieve Contractor of liability for damage which may result from moving of equipment.
1. State Route 64 is heavily used for visitor traffic and park operations. Traffic backups occur frequently, and specifically between hours of 10:00 a.m. and 2:00 p.m. year around, and 8:00 a.m. to 5:00 p.m. during peak periods, May through October. Contractor shall not impede flow of traffic and equipment and material deliveries at any time.
  2. Contractor shall use the south entrance gate and marked vehicles are allowed to use access road marked for "official use only" to bypass the ranger kiosks. The State Route 64 access to this bypass is near the kiosks and is subject to the same backups as visitor traffic entering the Park. Contractor personnel in marked vehicles are not required to pay Park entrance fees. Contractor shall not use the east entrance gate into the Park.
- J. Helicopter Drop-off Restrictions: South Rim WWTP periodically receives gaseous chlorine cylinders and waste from backcountry compostable toilets by helicopter drop off. Contractor activities in the helicopter drop-off area, which is within the Project area, shall be coordinated with the Government and not impede with WWTP operations.
- K. Vehicle Cleaning: Pressure wash and clean all construction vehicles and equipment as specified in Section 01 50 00, Temporary Facilities and Controls, before entering

the Park. Scheduled vehicle inspections are required prior to equipment entering the Park.

#### 1.8 PUBLIC USE OF SITE

- A. Contractor shall at all times conduct operations to ensure the least inconvenience to public.
- B. Kennel Road, the main access road to South Rim WWTP main entrance, Nursery and Grand Canyon Kennel, will be open to the public during construction. Contractor to minimize impact on access for public and NPS staff.
- C. Road closures may be permitted, when required, upon specific approval of Contracting Officer.

#### 1.9 OCCUPANCY REQUIREMENTS FOR BUILDINGS

##### A. Existing Buildings and Facilities:

- 1. Cooperate with Government during construction operations to minimize conflicts and facilitate Government usage. Perform Work so as not to interfere with Government's day-to-day operations. Maintain existing exits, unless otherwise indicated.
- 2. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Contracting Officer.

##### B. New Buildings:

- 1. Government Occupancy of Completed Areas of Construction: Government reserves right to occupy and to place and install equipment in completed areas of building, provided such occupancy does not interfere with completion of the Work. Such placement of equipment and partial occupancy shall not constitute acceptance of the entire Project.
  - a. Contracting Officer will prepare a Beneficial Occupancy letter for each specific portion of the Work to be occupied before Government occupancy.
  - b. Obtain a Certificate of Occupancy from National Park Service (NPS) before Government occupancy.
  - c. Before partial Government occupancy, building mechanical and electrical systems shall be fully operational, and required tests and inspections shall be successfully completed. On occupancy, Government will operate and maintain building mechanical and electrical systems serving occupied portions of building.
  - d. On occupancy, Government will assume responsibility for maintenance and custodial service for occupied portions of building.

## 1.10 CONDUCT OF OPERATIONS

- A. Contractor shall conduct his operations in conformance with rules and regulations promulgated by the Secretary of the Interior for the National Park Service, and applicable park rules and regulations prescribed by Park Superintendent.
- B. Work on Saturdays, Sundays, federal holidays, or at night may not be performed unless stated in the Work Restrictions below or without prior consent from the Contracting Officer. Submit requests 5 business days in advance of the work to the Contracting Officer for approval.
- C. No signs or advertisements (except those specified herein) shall be displayed on the construction Site or within the Park unless approved by the Contracting Officer.

## 1.11 WORK RESTRICTIONS

- A. Onsite Work Hours: Work shall be generally performed during normal business working hours of 6:00 a.m. to 6:00 p.m., Monday through Friday, except when otherwise indicated.
  - 1. Work on Federal Holidays must be approved by Contracting Officer.
  - 2. Weekend Hours: Specific work hours to be determined on a case-by-case basis when obtaining consent for weekend work from the Contracting Officer.
  - 3. Early Morning Hours: Specific work hours to be determined on a case-by-case basis and coordinated with the Contracting Officer.
  - 4. Hours for construction activities that require modification to existing treatment facilities, including but not limited to modifications to existing piping, utilities, electrical systems or tie-ins, shall be performed when South Rim WWTP facilities are staffed from 7:00 a.m. to 4:00 p.m. or as approved by Contracting Officer.
- B. Existing Utilities:
  - 1. Existing Utilities:
    - a. Notify Contracting Officer and utility companies of proposed locations and times for excavation.
    - b. Existing utilities shown on the Drawings are based on NPS provided data from previous projects and/or geographic information system data. Utilities have been surveyed where visible from the surface.
  - 2. Contractor shall be responsible for locating and preventing damage to known utilities. If damage occurs, repair utility at no additional expense to the Government.
  - 3. If damage occurs to an unknown utility, repair utility. An equitable adjustment will be made in accordance with the Changes clause of the contract.

C. Existing Utility Interruptions:

1. Do not interrupt utilities serving facilities occupied by Government or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
  - a. Notify Contracting Officer not less than 14 calendar days in advance of proposed utility interruptions.
  - b. Do not proceed with utility interruptions without Contracting Officer's written permission.
  - c. Hours and length of Utility Shutdowns: To be determined on a case-by-case basis with Contracting Officer. A contingency plan shall be in place to re-instate service if work cannot be completed as planned.

D. Nonsmoking Building/Tobacco Use/Vaping:

1. Smoking is not permitted within any building or within 25 feet of entrances, operable windows, or outdoor air intakes.
2. Due to concern of wildland fires, smoking is allowed only in a single designated area within the Contractor Support Facilities. This area shall be clear of exposed vegetation and have adequate means for disposal of trash and flammable materials. Contractor to maintain an appropriate cigarette butt collection system.

1.12 SPECIAL CONSTRUCTION REQUIREMENTS

- A. Project Website: A Project website administered by Contractor will be used for purposes of managing communication and documents during construction stage.
  1. See Section 01 31 00, Project Management and Coordination, for requirements on using Project Website.
- B. Hazardous Material: The South Rim WWTP facilities were tested for Asbestos containing material (ACM) and Lead-Based Paint (LBP.) The results and finding are contained in the report, "Hazardous Materials Investigation Report, Grand Canyon South Rim Wastewater Treatment Plant," November 2023 prepared by C J Seto Support Services. The Arizona Department of Environmental Quality (ADEQ) does not have separate state regulations for management disposal of ACM and LBP and therefore, refers to the applicable federal regulations. All handling and disposal of ACM or LBP must comply with current regulations. ADEQ does maintain notification forms for asbestos-containing material (ACM) renovation and demolition activities which are included for reference in the Asbestos and Lead Based Paint Sampling Report. If any LBP abatement or demolition activities are to take place, they shall conform to OSHA Lead in Construction regulations found in 29 CFR Part 1926.62 which require the employer provide worker protection.

### 1.13 SOILS INVESTIGATION REPORT

A. The following reports are available:

1. Preliminary Geotechnical Report, National Park Service – GRCA 257282, Replace Wastewater Plant South Rim Village, April 2022, prepared by Shannon & Wilson.
2. Geotechnical Report, Grand Canyon National Park – South Rim WWTP Access Road, South Rim Village, Arizona, December 2024, prepared by Shannon and Wilson.

B. Copies of reports are available to all plan holders with this package.

C. In case of conflict between report and the Drawings or Specifications, the Drawings and Specifications govern.

### 1.14 ADDITIONAL REPORTS

A. The following reports are available for reference:

1. Hazardous Materials Investigation Report, Grand Canyon South Rim Wastewater Treatment Plant, November 2023 prepared by C J Seto Support Services.

B. Copies of reports are available to all plan holders with this package.

C. In case of conflict between report and the Drawings or Specifications, the Drawings and Specifications govern.

### **PART 2 PRODUCTS (NOT USED)**

### **PART 3 EXECUTION (NOT USED)**

### **END OF SECTION**