

SECTION 01 57 19.12
NOISE AND ACOUSTICS MANAGEMENT

PART 1 GENERAL

1.1 SUMMARY

- A. Section Includes: Special requirements for noise and acoustics management during deconstruction, renovation, and construction operations.

1.2 DEFINITIONS

- A. Ambient Noise Level: The total noise associated with a given environment, being usually a composite of normal or existing sounds from all sources near and far, excluding the noise source at issue.
- B. Daytime: The hours from 7:00 a.m. to 9:00 p.m. on weekdays and 9:00 a.m. to 9:00 p.m. on weekends and holidays.
- C. Nighttime: All non-daytime hours.
- D. Property Line: The real or imaginary line along the ground surface and its vertical extension, which separates real property owned or controlled by one person from contiguous real property owned or controlled by another person or from any public right-of-way or from any public space.
- E. Receiving Noise Area: Any real property where people live or work and where noise is heard, excluding the Project or source area.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.1 NOISE MANAGEMENT

- A. Noise Control: Perform deconstruction, renovation, and construction operations to minimize noise. Perform noise-producing work in less sensitive hours of the day or week as directed by the Contracting Officer.
- B. Repetitive and/or Intermittent, High-level Noise: Permitted only during Daytime.
 - 1. Do not exceed the following dB(A) limitations at 50 feet:

<u>Sound Level in dB(A)</u>	<u>Time Duration of Impact Noise</u>
70	More than 12 minutes in any hour
80	More than 3 minutes in any hour

2. Maximum Permissible Construction Equipment Noise Levels at 50 Feet:

<u>EARTHMOVING</u>	<u>dB(A)</u>	<u>MATERIALS HANDLING</u>	<u>dB(A)</u>
Front Loaders	75	Concrete Mixers	75
Backhoes	75	Concrete Pumps	75
Dozers	75	Cranes	75
Tractors	75	Derricks Impact	75
Scrapers	80	Pile Drivers	95
Graders	75	Jack Hammers	75
Trucks	75	Rock Drills	80
Pavers, Stationary	80	Pneumatic Tools	80
Pumps	75	Saws	75
Generators	75	Vibrators	75
Compressors	75		

C. Ambient Noise:

1. Maximum noise levels (dB (decibel)) for receiving noise area at property lines shall be as follows:

a. Parking, Trailheads:

- 1) Daytime: 65 dB.
- 2) Nighttime: 45 dB.

b. Treatment Building Sites:

- 1) Daytime: 67 dB.
- 2) Nighttime: 65 dB.

c. In the event the existing local ambient noise level exceeds the maximum allowable receiving noise level (dB), the receiving noise level maximum for construction operations shall be adjusted as follows:

- 1) Parking, Trailheads: Maximum 3 additional dB above the local ambient as measured at property line.
- 2) Treatment Building Sites: Maximum 5 additional dB above the local ambient as measured at the property line.

3.2 FIELD QUALITY CONTROL

A. Assess potential effects of construction noise on adjacent neighbors and facility occupants in accordance with ASTM E1686 and as follows:

1. Ambient Noise Measurement: Measure at property line at a height of at least 4 feet above the immediate surrounding surface. Average the ambient noise level over a period of at least 15 minutes.

2. Ambient Noise Measurement at Urban Sites: Conduct during morning peak traffic hour between 7:00 a.m. and 9:00 a.m. and afternoon peak traffic hour between 4:00 p.m. and 6:00 p.m. In addition, conduct a 24-hour measurement at the proposed Project Site to document the noise pattern throughout the day. Adjust and weight for seasonal and climatic variations.
- B. Monitor noise produced from construction operations in accordance with ASTM E1780.

END OF SECTION

