



201 South 30th Street
Billings, Montana 59101
Phone: 406/245-7766
FAX: 406/254-1428

July 8, 2025

Ms. Laura Landon
Hennebery Eddy Architects, Inc.
921 SW Washinton Street, Suite 250
Portland, OR 97205

RE: Lead-Based Paint Survey 12 Buildings
 4 Lazy F Ranch
 4 Lazy F Ranch Road
 Moose, Wyoming
 Northern Industrial Hygiene Project No. 999-5237

Dear Ms. Landon:

This letter report provides the summarized results of the lead-based paint (LBP) survey conducted by Chris Hust of Northern Industrial Hygiene, Inc. (Northern) on May 20, 2025, and May 21, 2025, at the above referenced site. The survey was conducted to identify potential LBP and lead-containing paint (LCP) that may be present on the interior and exterior finishes of the 12 buildings that will be impacted by the upcoming renovation project.

Overview of Buildings

Harry's Cabin

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was moved to the site in 1954 but the construction date of the building is unknown. The building was previously used for housing.

Typical interior building materials include vinyl sheet and wood finished floors, log finished walls and wood finished ceilings. Base finishes were not present on the lower walls.

Exterior building finish materials consist of log siding and a rolled asphalt roofing. Both the walls and the roof are not insulated.

The building is heated by a wood burning fireplace. Water lines of the building are not insulated.

George's Cabin

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was constructed between 1927-1930's. The building was previously used for housing.

Typical interior building materials include vinyl sheet and wood finished floors, log finished walls and wood finished ceilings. Base finishes were not present on the lower walls.

Exterior building finish materials consist of log siding and a rolled asphalt roofing. Both the walls and the roof are not insulated.

The building is heated by a wood burning fireplace. Water lines of the building are not insulated.

End Cabin

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was constructed in 1927. The building was previously used for housing.

Typical interior building materials include vinyl sheet and wood finished floors, log finished walls and wood finished ceilings. Wood base finishes were present in the bathroom.

Exterior building finish materials consist of log siding and a rolled asphalt roofing. Both the walls and the roof are not insulated.

The building is heated by a wood burning fireplace. Water lines of the building are not insulated.

Mrs. Oliver's Cabin

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was constructed in 1927. The building was previously used for housing.

Typical interior building materials include vinyl sheet and wood finished floors, log and ceramic tile finished walls and wood finished ceilings. Wood base finishes were present in the bathroom.

Exterior building finish materials consist of log siding and a rolled asphalt roofing. Both the walls and the roof are not insulated.

The building is heated by a wood burning fireplace. Water lines of the building are not insulated.

Middle Cabin

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was constructed in 1927. The building was previously used for housing.

Typical interior building materials include vinyl sheet and wood finished floors, log and ceramic tile finished walls and wood finished ceilings. Wood base finishes were present in the bathroom.

Exterior building finish materials consist of log siding and a rolled asphalt roofing. Both the walls and the roof are not insulated.

The building is heated by a wood burning fireplace. Water lines of the building are not insulated.

River Cabin

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was moved to the site in 1961 but the construction date of the building is unknown. The building was previously used for housing.

Typical interior building materials include vinyl sheet and wood finished floors, log and gypsum board finished walls and wood finished ceilings. Base finishes were not present on the lower walls.

Exterior building finish materials consist of log siding and a rolled asphalt roofing. Both the walls and the roof are not insulated.

The building is heated by a wood burning fireplace. Water lines of the building are not insulated.

Nurse's Cabin

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was constructed between 1938-1967. The building was previously used for housing.

Typical interior building materials include vinyl sheet and wood finished floors, log, gypsum board, and plastic tile finished walls and wood and gypsum board finished ceilings. Lower walls in the bathroom, hallway, and storage room had vinyl bases.

Exterior building finish materials consist of log siding and a rolled asphalt roofing. The walls of the building were not insulated but ceilings in the center of the building were insulated with fiberglass insulation.

The building is heated by a wood burning fireplace. Water lines of the building are not insulated.

Main Lodge

The building is a one-story, wood siding, with a concrete foundation with crawlspace and partial basement located under the kitchen, and a pitched roof. The building was constructed in 1927. The building was previously used as the main lodging building on the site.

Typical interior building materials include vinyl sheet and wood finished floors, log and gypsum board finished walls and wood and gypsum board finished ceilings. Vinyl base finishes were present in the kitchen of the building.

Exterior building finish materials consist of log siding and a rolled asphalt roofing. Both the walls and the roof are not insulated.

The building is heated by a wood burning fireplace. Water lines of the building are not insulated.

Ice House

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was constructed in 1927. The building was previously used for the storage of ice for the site.

Typical interior building materials include metal floors, metal walls and metal finished ceiling. Base finishes were not present on the lower walls.

Exterior building finish materials consist of wood siding and a rolled asphalt roofing. Both the walls and the roof are insulated with saw dust insulation.

The building does not have a heating system. No water lines were present to the building.

Mouse House

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was constructed between 1938-1967. The building was previously used for storage.

Typical interior building materials include concrete finished floors, wood finished walls and wood finished ceiling. Lower walls are finished with a vinyl base.

Exterior building finish materials consist of wood siding and a rolled asphalt roofing. Both the walls and ceiling of the building are not insulated.

The building does not have a heating system. No water lines were present to the building.

New Cabin

Lead-Based Paint Survey

12 Buildings

4 Lazy F Ranch

Moose, Wyoming

July 8, 2025

Page 5 of 15

The building is a one-story wood siding, with a concrete masonry unit (CMU) block foundation, and a pitched roof. The building was constructed in 1964. The building was previously used for housing.

Typical interior building materials include wood floors, log walls and wood finished ceiling. Base finishes were not present on the lower walls.

Exterior building finish materials consist of log siding and a rolled asphalt roofing. Both the walls and the roof are not insulated.

The building is heated by a wood burning fireplace. Water lines of the building are not insulated.

3-Bay Garage

The building is a one-story, wood siding, with a slab-on-grade foundation, and a pitched roof. The building was constructed in 1938. The building was previously used as a garage.

Typical interior building materials include concrete floors and log walls. No ceiling was present at the time of the survey. Base finishes were not present on the lower walls.

Exterior building finish materials consist of log siding. No roof was present at the time of the survey. the walls are not insulated.

The building does not have a heating system. No water lines were present to the building.

Lead-Based Paint Overview

Lead is found in the paint on the inside and outside of many buildings. Most buildings constructed prior to World War II had LBP applied to the interior or exterior surfaces. Some paints introduced up until 1977 contained some level of lead. Regulations enforced by the Consumer Product Safety Commission (CPSC) banned the use of all but small amounts of lead in paints in 1978. However, manufacturers are still allowed to produce paints containing up to 90 parts per million (ppm) lead.

If the paint which contains lead is in poor or damaged condition, persons working or living in the area can be exposed to small paint chips or lead-containing dust. Exposure can also result from construction, demolition, repair and refinish (sanding) operations or from the torch cutting or burning of painted materials.

Exposure to the lead can also occur as a result of hobbies or sports. Individuals who work with lead while making stained glass or while melting lead to make sinkers or bullets, or individuals that reload ammunition are all exposed to varying levels of lead.

Lead-Based Paint Survey Procedures

The painted surfaces in this survey were analyzed for the presence of lead using a portable X-ray fluorescence instrument (XRF) manufactured for paint analysis. Portable XRF instruments expose the painted surface(s) to X-rays that cause lead to fluoresce with a characteristic frequency. The intensity of this fluorescence is measured by the instrument's detector and is then converted into a number that represents the amount of lead in the paint per unit area (milligrams per square centimeter (mg/cm²)). The XRF instrument has the capability to analyze the lead content of multiple layers of paint at one time.

For labeling and definition purposes in this report, the term LBP means paint or other surface coatings that contain lead at a concentration equal to or greater than 1.0 mg/cm² as measured using an XRF. This definition is utilized by the Department of Housing and Urban Development (HUD) and does not specifically apply to exposure concerns under the Occupational Safety and Health Administration (OSHA). The term lead-containing paint (LCP) means paint or other surface coatings that contain detectable lead at a concentration less than 1.0 mg/cm² as measured using an XRF.

OSHA regulates employee exposure to lead regardless of the concentration of lead in the material or the material containing lead. The definition of LBP in this report should be used only to discriminate paint with relatively high lead content from paint with relatively low lead content.

Lead-Based Paint Survey Findings

Harry's Cabin

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Fourteen painted building components were identified.

LBP was not detected on any of the components tested.

LCP was detected on 11 of the components tested. These components are:

- LHA-1 Wood Siding
- LHA-2 Wood Window Casing (Exterior)
- LHA-4 Wood Door (Exterior)
- LHA-5 Wood Door Casing (Exterior)
- LHA-6 Wood Soffit
- LHA-8 Wood Door
- LHA-9 Wood Door Casing
- LHA-10 Wood Window Casing

Lead-Based Paint Survey

12 Buildings

4 Lazy F Ranch

Moose, Wyoming

July 8, 2025

Page 7 of 15

- LHA-11 Wood Window Sash
- LHA-13 Wood Floor
- LHA-14 Wood Baseboard

Reference Table 1A for a description of identified painted building components and XRF screening results and Table 2A for individual XRF test readings.

George's Cabin

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Twelve painted building components were identified.

LBP was not detected on any of the components tested.

LCP was detected on one (1) of the components tested. This component is:

- LHA-1 Wood Siding

Reference Table 1B for a description of identified painted building components and XRF screening results and Table 2B for individual XRF test readings.

End Cabin

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Thirteen painted building components were identified.

LBP was detected on five (5) of the components tested. These components are:

- LHA-2 Wood Door (Exterior)
- LHA-3 Wood Door Casing (Exterior)
- LHA-4 Wood Window Casing (Exterior)
- LHA-5 Wood Window Sash (Exterior)
- LHA-11 Wood Window Sash

LCP was detected on seven (7) of the components tested. These components are:

- LHA-1 Wood Siding
- LHA-7 Wood Wall

Lead-Based Paint Survey

12 Buildings

4 Lazy F Ranch

Moose, Wyoming

July 8, 2025

Page 8 of 15

- LHA-8 Wood Door
- LHA-9 Wood Door Casing
- LHA-10 Wood Window Casing
- LHA-12 Wood Ceiling
- LHA-13 Wood Baseboard

Reference Table 1C for a description of identified painted building components and XRF screening results and Table 2C for individual XRF test readings.

Mrs. Oliver's Cabin

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Fourteen painted building components were identified.

LBP was detected on six (6) of the components tested. These components are:

- LHA-5 Wood Window Sash
- LHA-9 Wood Door (Exterior)
- LHA-10 Wood Door Casing (Exterior)
- LHA-11 Wood Window Casing (Exterior)
- LHA-12 Wood Window Sash (Exterior)
- LHA-14 Wood Crawlspace Hatch

LCP was detected on seven (7) of the components tested. These components are:

- LHA-1 Wood Wall
- LHA-2 Wood Door
- LHA-3 Wood Door Casing
- LHA-4 Wood Window Casing
- LHA-6 Wood Ceiling
- LHA-7 Wood Baseboard
- LHA-8 Wood Siding

Reference Table 1D for a description of identified painted building components and XRF screening results and Table 2D for individual XRF test readings.

Middle Cabin

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Twelve painted building components were identified.

LBP was detected on five (5) of the components tested. These components are:

- LHA-2 Wood Door (Exterior)
- LHA-3 Wood Door Casing (Exterior)
- LHA-4 Wood Window Casing (Exterior)
- LHA-5 Wood Window Sash (Exterior)
- LHA-12 Wood Window Sash

LCP was detected on six (6) of the components tested. These components are:

- LHA-1 Wood Siding
- LHA-7 Wood Wall
- LHA-8 Wood Door
- LHA-9 Wood Door Casing
- LHA-10 Wood Ceiling
- LHA-11 Wood Window Casing

Reference Table 1E for a description of identified painted building components and XRF screening results and Table 2E for individual XRF test readings.

River Cabin

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Nineteen painted building components were identified.

LBP was not detected on any of the components tested.

LCP was detected on 12 of the components tested. These components are:

- LHA-1 Wood Porch Rail
- LHA-2 Wood Porch Floor
- LHA-3 Wood Porch Column
- LHA-5 Wood Porch Beam
- LHA-6 Wood Window Casing (Exterior)
- LHA-7 Wood Window Sill (Exterior)
- LHA-8 Wood Door (Exterior)
- LHA-10 Metal Propane Tank
- LHA-11 Wood Siding

Lead-Based Paint Survey

12 Buildings

4 Lazy F Ranch

Moose, Wyoming

July 8, 2025

Page 10 of 15

- LHA-13 Wood Wall
- LHA-16 Wood Door
- LHA-19 Wood Window Sill

Reference Table 1F for a description of identified painted building components and XRF screening results and Table 2F for individual XRF test readings.

Nurse's Cabin

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Fourteen painted building components were identified.

LBP was detected on two (2) of the components tested. These components are:

- LHA-12 Wood Door Casing (Exterior)
- LHA-14 Wood Window Casing (Exterior)

LCP was detected on nine (9) of the components tested. These components are:

- LHA-2 Drywall Wall
- LHA-3 Wood Door
- LHA-4 Wood Door Casing
- LHA-5 Wood Window Casing
- LHA-6 Wood Window Sill
- LHA-8 Drywall Ceiling
- LHA-9 Wood Floor
- LHA-10 Wood Siding
- LHA-11 Wood Door

Reference Table 1G for a description of identified painted building components and XRF screening results and Table 2G for individual XRF test readings.

Main Lodge

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Sixteen painted building components were identified.

LBP was detected on five (5) of the components tested. These components are:

- LHA-6 Wood Window Sash
- LHA-12 Wood Door (Exterior)
- LHA-13 Wood Door Casing (Exterior)
- LHA-14 Wood Window Casing (Exterior)
- LHA-15 Wood Window Sash (Exterior)

LCP was detected on 10 of the components tested. These components are:

- LHA-1 Wood Wall
- LHA-2 Drywall Wall
- LHA-3 Wood Door
- LHA-4 Wood Door Casing
- LHA-5 Wood Window Casing
- LHA-7 Wood Floor
- LHA-9 Drywall Ceiling
- LHA-10 Wood Cabinet
- LHA-11 Wood Siding
- LHA-16 Wood Soffit

Reference Table 1H for a description of identified painted building components and XRF screening results and Table 2H for individual XRF test readings.

Ice House

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Ten painted building components were identified.

LBP was not detected on any of the components tested.

LCP was detected on four (4) of the components tested. These components are:

- LHA-1 Wood Siding
- LHA-8 Metal Cooler
- LHA-9 Metal Cooler Door
- LHA-10 Metal Propane Tank

Reference Table 1I for a description of identified painted building components and XRF screening results and Table 2I for individual XRF test readings.

Mouse House

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Four (4) painted building components were identified.

LBP was not detected on any of the components tested.

LCP was not detected on any of the components tested.

Reference Table 1J for a description of identified painted building components and XRF screening results and Table 2J for individual XRF test readings.

New Cabin

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Thirteen painted building components were identified.

LBP was not detected on any of the components tested.

LCP was detected on six (6) of the components tested. These components are:

- LHA-7 Wood Wall
- LHA-8 Wood Ceiling
- LHA-9 Wood Door
- LHA-10 Wood Door Casing
- LHA-11 Wood Window Casing
- LHA-12 Wood Window Sash

Reference Table 1K for a description of identified painted building components and XRF screening results and Table 2K for individual XRF test readings.

3-Bay Garage

This survey focused on identifying and testing painted surfaces on the interior and exterior of the building and testing these painted components for the presence or absence of LBP and LCP.

Two (2) painted building components were identified.

LBP was not detected on any of the components tested.

LCP was detected on two of the components tested. These components are:

- LHA-1 Wood Wall
- LHA-2 Wood Siding

Reference Table 1L for a description of identified painted building components and XRF screening results and Table 2L for individual XRF test readings.

Conclusions and Recommendations

Lead-Based Paint

LBP was detected on 5 of the components tested on the End Cabin, on 6 of the components tested on Mrs. Oliver's Cabin, on 6 of the components tested on the Middle Cabin, on 2 of the components tested on the Nurse's Cabin, and on 5 of the components tested on the Main Lodge. The LBP coated surfaces identified in this survey varied in condition from fair to poor (deteriorating). Northern recommends that contractors working with the materials be provided a copy of this report. Contractors disturbing painted surfaces of residences and child-occupied facilities constructed prior to 1978 must comply with the United States Environmental Protection Agency's (USEPA) Renovation, Repair and Painting (RRP) rule and the appropriate OSHA regulations.

Lead-Containing Paint

LCP was detected on 11 of the components tested on Harry's Cabin, on 1 of the components tested on George's Cabin, on 7 of the components tested on the End Cabin, on 7 of the components tested on Mrs. Oliver's Cabin, on 6 of the components tested on the Middle Cabin, on 12 of the components tested on the River Cabin, on 9 of the components tested on the Nurse's Cabin, on 10 of the components tested on the Main Lodge, on 4 of the components tested on the Ice House, on 6 of the components tested on the New Cabin, and on 2 of the components tested on the 3-Bay Garage. The LCP coated surfaces identified in this limited survey varied in condition from intact to poor (deteriorating). Work involving components covered with paint containing lead (lead-based and LCP) is subject to OSHA regulations. The disposal of lead containing materials is subject to USEPA regulations.

The LCP coated surfaces identified in this limited survey varied in condition from intact to poor (deteriorating). Lead-containing surface coatings that are in intact or fair condition that will not be disturbed do not pose a hazard to employees. Lead-containing surface coatings that are disturbed in a manner described below or lead-containing surface coatings that are in poor condition (cracked, deteriorated, dusting or peeling) may result in a hazardous condition and will need to be addressed according to OSHA regulations.

The OSHA standard for Lead in Construction, 29 CFR 1926, does not recognize a safe level of lead in dried paint to which workers may be exposed in an occupational setting. Consequently, any disturbance to painted surfaces which contain a measurable quantity of lead must be considered as having the potential to create a risk to workers.

The OSHA standard cites a Permissible Exposure Level (PEL) of 50 micrograms of lead per cubic meter of air ($\mu\text{g}/\text{m}^3$) and an Action Level (AL) of 30 $\mu\text{g}/\text{m}^3$.

If an employee is performing any of the following tasks involving LCPs:

1. Manual demolition, dry scraping, or dry sanding;
2. Heat gun applications;
3. Power tool cleaning;
4. Other industrial operations involving lead as specified in the OSHA standards; then

the employee must be presumed to be exposed to lead at a concentration above the permissible exposure limit (PEL) unless the employer has a negative exposure assessment (NEA) for this type of work.

If the employer does not have a NEA, the following safety and health provisions must be implemented:

1. Respiratory protection program requirements
2. Use of personal protective clothing and equipment
3. Designated changing areas including segregated storage of work and non-work clothing
4. Hand-washing facilities
5. Blood testing
6. Employee training

Northern recommends that contractors working with the materials be provided a copy of this report.

Limitations

This LBP survey report was prepared based on information obtained during our on-site observations and interpretation of the XRF data collected during the survey. The conclusions of this report are professional opinions based solely upon review of our visual site observations and interpretations of field data as described in our report.

Lead-Based Paint Survey
12 Buildings
4 Lazy F Ranch
Moose, Wyoming
July 8, 2025
Page 15 of 15

This report has been prepared to provide information concerning the interior and exterior painted building components tested and the locations of any components identified as having LBP present or LCP, if any. It includes only those components that were visible and accessible at the time of our inspection. Northern did not remove any permanent building enclosures or disassemble any equipment.

This survey report is intended to identify LBP and LCP coated building components. It is not intended to be used for the purpose of obtaining bids for their removal by abatement contractors. The scope of services performed by Northern may not be appropriate to satisfy the needs of other users, and any use or re-use of this document, or the findings presented herein, is at the sole risk of the user.

Our opinions are intended exclusively for use by Hennebery Eddy Architects Inc. and the building owner. The opinions presented herein apply to the site conditions existing at the time of our survey. Therefore, the opinions and recommendations in this report may not apply to future conditions that may exist at the site that Northern has not had the opportunity to evaluate.

We trust this summary report provides sufficient information for planning purposes. We appreciate the opportunity to assist you and look forward to continuing to work with you.

If you have any questions or require additional information, please contact us.

Respectfully submitted,

NORTHERN INDUSTRIAL HYGIENE, INC.

A handwritten signature in black ink, appearing to read "Christopher Hunt", with a long horizontal flourish extending to the right.

Chris Hust
Environmental Technician
EPA Lead Paint Inspector

Attachments: Table Sets 1 and 2
LBP Location Drawings
Certifications

TABLE 1A
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS
4 Lazy F Ranch - Harry's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Siding	Wood	Stain	Fair	LCP
LHA-2	Window Casing (Exterior)	Wood	Brown	Fair	LCP
LHA-3	Window Sash (Exterior)	Wood	Brown	Fair	NEG
LHA-4	Door (Exterior)	Wood	Brown	Fair	LCP
LHA-5	Door Casing (Exterior)	Wood	Brown	Fair	LCP
LHA-6	Soffit	Wood	Stain	Fair	LCP
LHA-7	Wall	Wood	Stain	Fair	NEG
LHA-8	Door	Wood	Stain	Fair	LCP
LHA-9	Door Casing	Wood	Stain	Fair	LCP
LHA-10	Window Casing	Wood	Stain	Fair	LCP
LHA-11	Window Sash	Wood	Stain	Fair	LCP
LHA-12	Ceiling	Wood	White	Fair	NEG
LHA-13	Floor	Wood	Brown	Fair	LCP
LHA-14	Baseboard	Wood	Brown	Fair	LCP

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* NEG = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2A for test locations of confirmed building components, if any.

TABLE 1B
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS

Lazy F Ranch - George's Cabin
 4 Lazy F Ranch Road
 Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Siding	Wood	Stain	Fair	LCP
LHA-2	Door (Exterior)	Wood	Stain	Fair	NEG
LHA-3	Door Casing (Exterior)	Wood	Stain	Fair	NEG
LHA-4	Window Casing (Exterior)	Wood	Stain	Fair	NEG
LHA-5	Window Sill (Exterior)	Wood	Stain	Fair	NEG
LHA-6	Soffit	Wood	Stain	Fair	NEG
LHA-7	Wall	Wood	Stain	Fair	NEG
LHA-8	Ceiling	Wood	Stain	Fair	NEG
LHA-9	Door	Wood	Stain	Fair	NEG
LHA-10	Door Casing	Wood	Stain	Fair	NEG
LHA-11	Window Casing	Wood	Stain	Fair	NEG
LHA-12	Window Sash	Wood	Stain	Fair	NEG

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* NEG = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2B for test locations of confirmed building components, if any.

TABLE 1C
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS

4 Lazy F Ranch - End Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Siding	Wood	Stain	Fair	LCP
LHA-2	Door (Exterior)	Wood	Brown	Fair	LBP
LHA-3	Door Casing (Exterior)	Wood	Brown	Fair	LBP
LHA-4	Window Casing (Exterior)	Wood	Brown	Fair	LBP
LHA-5	Window Sash (Exterior)	Wood	Brown	Fair	LBP
LHA-6	Soffit	Wood	Stain	Fair	NEG
LHA-7	Wall	Wood	Stain	Fair	LCP
LHA-8	Door	Wood	Stain	Fair	LCP
LHA-9	Door Casing	Wood	Stain	Fair	LCP
LHA-10	Window Casing	Wood	Stain	Fair	LCP
LHA-11	Window Sash	Wood	Brown, Stain	Fair	LBP
LHA-12	Ceiling	Wood	Stain	Fair	LCP
LHA-13	Baseboard	Wood	Stain	Fair	LCP

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* **NEG** = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2C for test locations of confirmed building components, if any.

TABLE 1D
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS
4 Lazy F Ranch - Mrs. Oliver's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Wall	Wood	Stain	Fair	LCP
LHA-2	Door	Wood	Stain	Fair	LCP
LHA-3	Door Casing	Wood	Stain	Fair	LCP
LHA-4	Window Casing	Wood	Stain	Fair	LCP
LHA-5	Window Sash	Wood	Brown, Stain	Fair	LBP
LHA-6	Ceiling	Wood	White, Stain	Fair	LCP
LHA-7	Baseboard	Wood	Stain	Fair	LCP
LHA-8	Siding	Wood	Stain	Fair	LCP
LHA-9	Door (Exterior)	Wood	Brown	Fair	LBP
LHA-10	Door Casing (Exterior)	Wood	Brown	Fair	LBP
LHA-11	Window Casing (Exterior)	Wood	Brown	Fair	LBP
LHA-12	Window Sash (Exterior)	Wood	Brown	Fair	LBP
LHA-13	Soffit	Wood	Stain	Fair	NEG
LHA-14	Crawlspace Hatch	Wood	Brown	Fair	LBP

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* **NEG** = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2D for test locations of confirmed building components, if any.

TABLE 1E
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS
4 Lazy F Ranch - Middle Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Siding	Wood	Stain	Fair	LCP
LHA-2	Door (Exterior)	Wood	Brown	Poor	LBP
LHA-3	Door Casing (Exterior)	Wood	Brown	Poor	LBP
LHA-4	Window Casing (Exterior)	Wood	Brown	Poor	LBP
LHA-5	Window Sash (Exterior)	Wood	Brown	Poor	LBP
LHA-6	Soffit	Wood	Stain	Fair	NEG
LHA-7	Wall	Wood	Stain	Fair	LCP
LHA-8	Door	Wood	Stain	Fair	LCP
LHA-9	Door Casing	Wood	Stain	Fair	LCP
LHA-10	Ceiling	Wood	White, Stain	Fair	LCP
LHA-11	Window Casing	Wood	Stain	Fair	LCP
LHA-12	Window Sash	Wood	Brown, Stain	Fair	LBP

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* **NEG** = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2E for test locations of confirmed building components, if any.

TABLE 1F
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS
4 Lazy F Ranch - River Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Porch Rail	Wood	Brown	Poor	LCP
LHA-2	Porch Floor	Wood	Brown	Poor	LCP
LHA-3	Porch Column	Wood	Brown	Poor	LCP
LHA-4	Steps	Wood	Brown	Poor	NEG
LHA-5	Porch Beam	Wood	Brown	Poor	LCP
LHA-6	Window Casing (Exterior)	Wood	Brown	Poor	LCP
LHA-7	Window Sill (Exterior)	Wood	Brown	Poor	LCP
LHA-8	Door (Exterior)	Wood	Stain	Poor	LCP
LHA-9	Door Casing (Exterior)	Wood	Brown	Poor	NEG
LHA-10	Propane Tank	Metal	White	Poor	LCP
LHA-11	Siding	Wood	Stain	Poor	LCP
LHA-12	Soffit	Wood	Stain	Poor	NEG
LHA-13	Wall	Wood	Stain	Fair	LCP
LHA-14	Wall	Drywall	White	Fair	NEG
LHA-15	Ceiling	Wood	Stain	Fair	NEG
LHA-16	Door	Wood	Stain	Fair	LCP
LHA-17	Floor	Wood	Stain	Fair	NEG
LHA-18	Window Casing	Wood	Stain	Fair	NEG
LHA-19	Window Sill	Wood	Stain	Fair	LCP

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* **NEG** = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2F for test locations of confirmed building components, if any.

TABLE 1G
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS
4 Lazy F Ranch - Nurse's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Wall	Wood	Stain	Fair	NEG
LHA-2	Wall	Drywall	White	Fair	LCP
LHA-3	Door	Wood	Stain	Fair	LCP
LHA-4	Door Casing	Wood	Stain	Fair	LCP
LHA-5	Window Casing	Wood	Stain	Fair	LCP
LHA-6	Window Sill	Wood	Stain	Fair	LCP
LHA-7	Ceiling	Wood	Stain	Fair	NEG
LHA-8	Ceiling	Drywall	White	Fair	LCP
LHA-9	Floor	Wood	Stain, Brown	Fair	LCP
LHA-10	Siding	Wood	Stain	Fair	LCP
LHA-11	Door (Exterior)	Wood	Stain	Fair	LCP
LHA-12	Door Casing (Exterior)	Wood	Brown	Fair	LBP
LHA-13	Soffit	Wood	Stain	Fair	NEG
LHA-14	Window Casing (Exterior)	Wood	Stain, Brown	Fair	LBP

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* **NEG** = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2G for test locations of confirmed building components, if any.

TABLE 1H
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS
4 Lazy F Ranch - Main Lodge
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Wall	Wood	Stain	Poor	LCP
LHA-2	Wall	Drywall	White	Poor	LCP
LHA-3	Door	Wood	Stain	Poor	LCP
LHA-4	Door Casing	Wood	Stain	Poor	LCP
LHA-5	Window Casing	Wood	Stain	Poor	LCP
LHA-6	Window Sash	Wood	Stain, Brown	Poor	LBP
LHA-7	Floor	Wood	Brown, Gray	Poor	LCP
LHA-8	Ceiling	Wood	Stain	Poor	NEG
LHA-9	Ceiling	Drywall	White	Poor	LCP
LHA-10	Cabinet	Wood	Stain	Poor	LCP
LHA-11	Siding	Wood	Stain	Poor	LCP
LHA-12	Door (Exterior)	Wood	Brown	Poor	LBP
LHA-13	Door Casing (Exterior)	Wood	Brown	Poor	LBP
LHA-14	Window Casing	Wood	Brown	Poor	LBP
LHA-15	Window Sash	Wood	Brown	Poor	LBP
LHA-16	Soffit	Wood	Brown	Poor	LCP

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* **NEG** = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2H for test locations of confirmed building components, if any.

TABLE 11
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS
4 Lazy F Ranch - Ice House
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Siding	Wood	Stain	Fair	LCP
LHA-2	Door (Exterior)	Wood	Stain	Fair	NEG
LHA-3	Door Casing (Exterior)	Wood	Stain	Fair	NEG
LHA-4	Soffit	Wood	Stain	Fair	NEG
LHA-5	Wall	Wood	Stain	Fair	NEG
LHA-6	Ceiling	Wood	Stain	Fair	NEG
LHA-7	Door	Wood	Stain	Fair	NEG
LHA-8	Cooler	Metal	Gray, Silver	Fair	LCP
LHA-9	Cooler Door	Metal	Gray, Silver	Fair	LCP
LHA-10	Propane Tank	Metal	White	Fair	LCP

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* **NEG** = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 21 for test locations of confirmed building components, if any.

TABLE 1J
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS
4 Lazy F Ranch - Mouse House
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Siding	Wood	Stain	Fair	NEG
LHA-2	Door (Exterior)	Wood	Stain	Fair	NEG
LHA-3	Door Casing (Exterior)	Wood	Stain	Fair	NEG
LHA-4	Soffit	Wood	Stain	Fair	NEG

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* NEG = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2J for test locations of confirmed building components, if any.

TABLE 1K
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS

4 Lazy F Ranch - New Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Siding	Wood	Stain	Fair	NEG
LHA-2	Door (Exterior)	Wood	Stain	Fair	NEG
LHA-3	Door Casing (Exterior)	Wood	Stain	Fair	NEG
LHA-4	Window Casing (Exterior)	Wood	Stain	Fair	NEG
LHA-5	Window Sash (Exterior)	Wood	Stain	Fair	NEG
LHA-6	Soffit	Wood	Stain	Fair	NEG
LHA-7	Wall	Wood	Stain	Fair	LCP
LHA-8	Ceiling	Wood	Stain	Fair	LCP
LHA-9	Door	Wood	Stain	Fair	LCP
LHA-10	Door Casing	Wood	Stain	Fair	LCP
LHA-11	Window Casing	Wood	Stain	Fair	LCP
LHA-12	Window Sash	Wood	Stain	Fair	LCP
LHA-13	Floor	Wood	Stain	Fair	NEG

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* NEG = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2K for test locations of confirmed building components, if any.

TABLE 1L
IDENTIFIED PAINTED BUILDING COMPONENTS XRF SCREENING RESULTS
4 Lazy F Ranch - 3-Bay Garage
4 Lazy F Ranch Road
Moose, Wyoming

Material Number	Building Component	Substrate	Color (at time of survey)	Material Condition	Screening Result*
LHA-1	Wall	Wood	Stain	Poor	LCP
LHA-2	Siding	Wood	Stain	Poor	LCP

* **LBP** = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* **LCP** = Lead-containing paint- one or more items tested contain detectable lead at concentrations less than 1.0 mg/cm² measured using XRF screening.

* **NEG** = Negative - no tested items contained detectable lead measured using XRF screening.

** Reference Table 2L for test locations of confirmed building components, if any.

TABLE 2A
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Harry's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	Harry's Cabin	N/A	Exterior	A	1	Siding	Wood	Stain	Fair	ND	NEG
2	Harry's Cabin	N/A	Exterior	B	1	Siding	Wood	Stain	Fair	ND	NEG
3	Harry's Cabin	N/A	Exterior	C	1	Siding	Wood	Stain	Fair	ND	NEG
4	Harry's Cabin	N/A	Exterior	D	1	Siding	Wood	Stain	Fair	0.01	LCP
5	Harry's Cabin	N/A	Exterior	A	2	Window Casing	Wood	Brown	Fair	ND	NEG
6	Harry's Cabin	N/A	Exterior	B	2	Window Casing	Wood	Brown	Fair	0.01	LCP
7	Harry's Cabin	N/A	Exterior	D	2	Window Casing	Wood	Brown	Fair	ND	NEG
8	Harry's Cabin	N/A	Exterior	A	3	Window Sash	Wood	Brown	Fair	ND	NEG
9	Harry's Cabin	N/A	Exterior	B	3	Window Sash	Wood	Brown	Fair	ND	NEG
10	Harry's Cabin	N/A	Exterior	D	3	Window Sash	Wood	Brown	Fair	ND	NEG
11	Harry's Cabin	N/A	Exterior	C	4	Door	Wood	Brown	Fair	0.08	LCP
12	Harry's Cabin	N/A	Exterior	C	5	Door Casing	Wood	Brown	Fair	0.09	LCP
13	Harry's Cabin	N/A	Exterior	A	6	Soffit	Wood	Stain	Fair	ND	NEG
14	Harry's Cabin	N/A	Exterior	B	6	Soffit	Wood	Stain	Fair	ND	NEG
15	Harry's Cabin	N/A	Exterior	C	6	Soffit	Wood	Stain	Fair	0.01	LCP
16	Harry's Cabin	N/A	Exterior	D	6	Soffit	Wood	Stain	Fair	ND	NEG
17	Harry's Cabin	N/A	Bedroom	A	7	Wall	Wood	Stain	Fair	ND	NEG
18	Harry's Cabin	N/A	Bedroom	B	7	Wall	Wood	Stain	Fair	ND	NEG
19	Harry's Cabin	N/A	Bedroom	C	7	Wall	Wood	Stain	Fair	ND	NEG
20	Harry's Cabin	N/A	Bedroom	D	7	Wall	Wood	Stain	Fair	ND	NEG
21	Harry's Cabin	N/A	Bathroom	A	7	Wall	Wood	Stain	Fair	ND	NEG
22	Harry's Cabin	N/A	Bathroom	B	7	Wall	Wood	Stain	Fair	ND	NEG
23	Harry's Cabin	N/A	Bathroom	C	7	Wall	Wood	Stain	Fair	ND	NEG
24	Harry's Cabin	N/A	Bathroom	D	7	Wall	Wood	Stain	Fair	ND	NEG
25	Harry's Cabin	N/A	Bedroom	C	8	Door	Wood	Stain	Fair	ND	NEG
26	Harry's Cabin	N/A	Bedroom	C	9	Door Casing	Wood	Stain	Fair	0.04	LCP
27	Harry's Cabin	N/A	Bathroom	C	8	Door	Wood	Stain	Fair	0.03	LCP
28	Harry's Cabin	N/A	Bathroom	C	9	Door Casing	Wood	Stain	Fair	0.04	LCP

TABLE 2A
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Harry's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
29	Harry's Cabin	N/A	Bedroom	B	10	Window Casing	Wood	Stain	Fair	0.01	LCP
30	Harry's Cabin	N/A	Bathroom	A	10	Window Casing	Wood	Stain	Fair	0.01	LCP
31	Harry's Cabin	N/A	Bedroom	D	11	Window Sash	Wood	Stain	Fair	ND	NEG
32	Harry's Cabin	N/A	Bathroom	A	11	Window Sash	Wood	Stain	Fair	0.01	LCP
33	Harry's Cabin	N/A	Bedroom	N/A	12	Ceiling	Wood	White	Fair	ND	NEG
34	Harry's Cabin	N/A	Bathroom	N/A	12	Ceiling	Wood	White	Fair	ND	NEG
35	Harry's Cabin	N/A	Bathroom	N/A	13	Floor	Wood	Brown	Fair	0.01	LCP
36	Harry's Cabin	N/A	Bathroom	C	14	Baseboard	Wood	Brown	Fair	0.05	LCP
37	Harry's Cabin	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.06	LBP
38	Harry's Cabin	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.03	LBP
39	Harry's Cabin	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.11	LBP

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2B
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - George's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	George's Cabin	N/A	Exterior	A	1	Siding	Wood	Stain	Fair	ND	NEG
2	George's Cabin	N/A	Exterior	B	1	Siding	Wood	Stain	Fair	ND	NEG
3	George's Cabin	N/A	Exterior	C	1	Siding	Wood	Stain	Fair	0.02	LCP
4	George's Cabin	N/A	Exterior	D	1	Siding	Wood	Stain	Fair	ND	NEG
5	George's Cabin	N/A	Exterior	D	2	Door	Wood	Stain	Fair	ND	NEG
6	George's Cabin	N/A	Exterior	D	3	Door Casing	Wood	Stain	Fair	ND	NEG
7	George's Cabin	N/A	Exterior	D	4	Window Casing	Wood	Stain	Fair	ND	NEG
8	George's Cabin	N/A	Exterior	B	4	Window Casing	Wood	Stain	Fair	ND	NEG
9	George's Cabin	N/A	Exterior	D	5	Window Sill	Wood	Stain	Fair	ND	NEG
10	George's Cabin	N/A	Exterior	B	5	Window Sill	Wood	Stain	Fair	ND	NEG
11	George's Cabin	N/A	Exterior	A	6	Soffit	Wood	Stain	Fair	ND	NEG
12	George's Cabin	N/A	Exterior	B	6	Soffit	Wood	Stain	Fair	ND	NEG
13	George's Cabin	N/A	Exterior	C	6	Soffit	Wood	Stain	Fair	ND	NEG
14	George's Cabin	N/A	Exterior	D	6	Soffit	Wood	Stain	Fair	ND	NEG
15	George's Cabin	N/A	Entry	A	7	Wall	Wood	Stain	Fair	ND	NEG
16	George's Cabin	N/A	Entry	B	7	Wall	Wood	Stain	Fair	ND	NEG
17	George's Cabin	N/A	Entry	C	7	Wall	Wood	Stain	Fair	ND	NEG
18	George's Cabin	N/A	Entry	D	7	Wall	Wood	Stain	Fair	ND	NEG
19	George's Cabin	N/A	Bedroom	A	7	Wall	Wood	Stain	Fair	ND	NEG
20	George's Cabin	N/A	Bedroom	B	7	Wall	Wood	Stain	Fair	ND	NEG
21	George's Cabin	N/A	Bedroom	C	7	Wall	Wood	Stain	Fair	ND	NEG
22	George's Cabin	N/A	Bedroom	D	7	Wall	Wood	Stain	Fair	ND	NEG
23	George's Cabin	N/A	Bathroom	A	7	Wall	Wood	Stain	Fair	ND	NEG
24	George's Cabin	N/A	Bathroom	B	7	Wall	Wood	Stain	Fair	ND	NEG
25	George's Cabin	N/A	Bathroom	C	7	Wall	Wood	Stain	Fair	ND	NEG
26	George's Cabin	N/A	Bathroom	D	7	Wall	Wood	Stain	Fair	ND	NEG
27	George's Cabin	N/A	Entry	N/A	8	Ceiling	Wood	Stain	Fair	ND	NEG
28	George's Cabin	N/A	Bedroom	N/A	8	Ceiling	Wood	Stain	Fair	ND	NEG

TABLE 2B
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - George's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
29	George's Cabin	N/A	Bathroom	N/A	8	Ceiling	Wood	Stain	Fair	ND	NEG
30	George's Cabin	N/A	Entry	D	9	Door	Wood	Stain	Fair	ND	NEG
31	George's Cabin	N/A	Bedroom	A	9	Door	Wood	Stain	Fair	ND	NEG
32	George's Cabin	N/A	Bathroom	C	9	Door	Wood	Stain	Fair	ND	NEG
33	George's Cabin	N/A	Entry	D	10	Door Casing	Wood	Stain	Fair	ND	NEG
34	George's Cabin	N/A	Bedroom	A	10	Door Casing	Wood	Stain	Fair	ND	NEG
35	George's Cabin	N/A	Bathroom	C	10	Door Casing	Wood	Stain	Fair	ND	NEG
36	George's Cabin	N/A	Bedroom	D	11	Window Casing	Wood	Stain	Fair	ND	NEG
37	George's Cabin	N/A	Bathroom	B	11	Window Casing	Wood	Stain	Fair	ND	NEG
38	George's Cabin	N/A	Bedroom	D	12	Window Sill	Wood	Stain	Fair	ND	NEG
39	George's Cabin	N/A	Bathroom	B	12	Window Sill	Wood	Stain	Fair	ND	NEG

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2C
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - End Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	End Cabin	N/A	Exterior	A	1	Siding	Wood	Stain	Fair	0.01	LCP
2	End Cabin	N/A	Exterior	B	1	Siding	Wood	Stain	Fair	0.02	LCP
3	End Cabin	N/A	Exterior	C	1	Siding	Wood	Stain	Fair	0.01	LCP
4	End Cabin	N/A	Exterior	D	1	Siding	Wood	Stain	Fair	ND	NEG
5	End Cabin	N/A	Exterior	A	2	Door	Wood	Brown	Poor	5.16	LBP
6	End Cabin	N/A	Exterior	A	3	Door Casing	Wood	Brown	Poor	5.77	LBP
7	End Cabin	N/A	Exterior	A	4	Window Casing	Wood	Brown	Poor	7.1	LBP
8	End Cabin	N/A	Exterior	C	4	Window Casing	Wood	Brown	Poor	7.92	LBP
9	End Cabin	N/A	Exterior	A	5	Window Sash	Wood	Brown	Poor	7.7	LBP
10	End Cabin	N/A	Exterior	C	5	Window Sash	Wood	Brown	Poor	6.56	LBP
11	End Cabin	N/A	Exterior	A	6	Soffit	Wood	Stain	Fair	ND	NEG
12	End Cabin	N/A	Exterior	B	6	Soffit	Wood	Stain	Fair	ND	NEG
13	End Cabin	N/A	Exterior	C	6	Soffit	Wood	Stain	Fair	ND	NEG
14	End Cabin	N/A	Exterior	D	6	Soffit	Wood	Stain	Fair	ND	NEG
15	End Cabin	N/A	W. Bedroom	A	7	Wall	Wood	Stain	Fair	ND	NEG
16	End Cabin	N/A	W. Bedroom	B	7	Wall	Wood	Stain	Fair	ND	NEG
17	End Cabin	N/A	W. Bedroom	C	7	Wall	Wood	Stain	Fair	ND	NEG
18	End Cabin	N/A	W. Bedroom	D	7	Wall	Wood	Stain	Fair	ND	NEG
19	End Cabin	N/A	Bathroom	A	7	Wall	Wood	Stain	Fair	0.01	LCP
20	End Cabin	N/A	Bathroom	B	7	Wall	Wood	Stain	Fair	ND	NEG
21	End Cabin	N/A	Bathroom	C	7	Wall	Wood	Stain	Fair	ND	NEG
22	End Cabin	N/A	Bathroom	D	7	Wall	Wood	Stain	Fair	0.02	LCP
23	End Cabin	N/A	E. Bedroom	A	7	Wall	Wood	Stain	Fair	ND	NEG
24	End Cabin	N/A	E. Bedroom	B	7	Wall	Wood	Stain	Fair	ND	NEG
25	End Cabin	N/A	E. Bedroom	C	7	Wall	Wood	Stain	Fair	ND	NEG
26	End Cabin	N/A	E. Bedroom	D	7	Wall	Wood	Stain	Fair	ND	NEG
27	End Cabin	N/A	W. Bedroom	A	8	Door	Wood	Stain	Fair	ND	NEG
28	End Cabin	N/A	Bathroom	A	8	Door	Wood	Stain	Fair	0.01	LCP

TABLE 2C
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - End Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
29	End Cabin	N/A	E. Bedroom	A	8	Door	Wood	Stain	Fair	ND	NEG
30	End Cabin	N/A	W. Bedroom	A	9	Door Casing	Wood	Stain	Fair	ND	NEG
31	End Cabin	N/A	Bathroom	A	9	Door Casing	Wood	Stain	Fair	0.01	LCP
32	End Cabin	N/A	E. Bedroom	A	9	Door Casing	Wood	Stain	Fair	ND	NEG
33	End Cabin	N/A	W. Bedroom	A	10	Window Casing	Wood	Stain	Fair	ND	NEG
34	End Cabin	N/A	Bathroom	C	10	Window Casing	Wood	Stain	Fair	0.01	LCP
35	End Cabin	N/A	E. Bedroom	A	10	Window Casing	Wood	Stain	Fair	ND	NEG
36	End Cabin	N/A	W. Bedroom	A	11	Window Sash	Wood	Brown	Fair	5.02	LBP
37	End Cabin	N/A	Bathroom	C	11	Window Sash	Wood	Stain	Fair	ND	NEG
38	End Cabin	N/A	E. Bedroom	A	11	Window Sash	Wood	Brown	Fair	6.78	LBP
39	End Cabin	N/A	W. Bedroom	N/A	12	Ceiling	Wood	Stain	Fair	0.02	LCP
40	End Cabin	N/A	Bathroom	N/A	12	Ceiling	Wood	Stain	Fair	ND	NEG
41	End Cabin	N/A	E. Bedroom	N/A	12	Ceiling	Wood	Stain	Fair	ND	NEG
42	End Cabin	N/A	Bathroom	D	13	Baseboard	Wood	Stain	Fair	0.01	LCP

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2D
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Mrs. Oliver's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	Mrs.Oliver's Cabin	N/A	W. Bedroom	A	1	Wall	Wood	Stain	Fair	ND	NEG
2	Mrs.Oliver's Cabin	N/A	W. Bedroom	B	1	Wall	Wood	Stain	Fair	ND	NEG
3	Mrs.Oliver's Cabin	N/A	W. Bedroom	C	1	Wall	Wood	Stain	Fair	ND	NEG
4	Mrs.Oliver's Cabin	N/A	W. Bedroom	D	1	Wall	Wood	Stain	Fair	ND	NEG
5	Mrs.Oliver's Cabin	N/A	Bathroom	A	1	Wall	Wood	Stain	Fair	0.03	LCP
6	Mrs.Oliver's Cabin	N/A	Bathroom	B	1	Wall	Wood	Stain	Fair	0.03	LCP
7	Mrs.Oliver's Cabin	N/A	Bathroom	C	1	Wall	Wood	Stain	Fair	0.03	LCP
8	Mrs.Oliver's Cabin	N/A	Bathroom	D	1	Wall	Wood	Stain	Fair	0.03	LCP
9	Mrs.Oliver's Cabin	N/A	E. Bedroom	A	1	Wall	Wood	Stain	Fair	ND	NEG
10	Mrs.Oliver's Cabin	N/A	E. Bedroom	B	1	Wall	Wood	Stain	Fair	ND	NEG
11	Mrs.Oliver's Cabin	N/A	E. Bedroom	C	1	Wall	Wood	Stain	Fair	ND	NEG
12	Mrs.Oliver's Cabin	N/A	E. Bedroom	D	1	Wall	Wood	Stain	Fair	ND	NEG
13	Mrs.Oliver's Cabin	N/A	W. Bedroom	A	2	Door	Wood	Stain	Fair	ND	NEG
14	Mrs.Oliver's Cabin	N/A	Bathroom	A	2	Door	Wood	Stain	Fair	0.01	LCP
15	Mrs.Oliver's Cabin	N/A	E. Bedroom	A	2	Door	Wood	Stain	Fair	ND	NEG
16	Mrs.Oliver's Cabin	N/A	W. Bedroom	A	3	Door Casing	Wood	Stain	Fair	0.02	LCP
17	Mrs.Oliver's Cabin	N/A	Bathroom	A	3	Door Casing	Wood	Stain	Fair	0.02	LCP
18	Mrs.Oliver's Cabin	N/A	E. Bedroom	A	3	Door Casing	Wood	Stain	Fair	0.04	LCP
19	Mrs.Oliver's Cabin	N/A	W. Bedroom	C	4	Window Casing	Wood	Stain	Fair	0.06	LCP
20	Mrs.Oliver's Cabin	N/A	Bathroom	C	4	Window Casing	Wood	Stain	Fair	0.04	LCP
21	Mrs.Oliver's Cabin	N/A	E. Bedroom	A	4	Window Casing	Wood	Stain	Fair	0.1	LCP
22	Mrs.Oliver's Cabin	N/A	W. Bedroom	C	5	Window Sash	Wood	Brown	Fair	5.41	LBP
23	Mrs.Oliver's Cabin	N/A	Bathroom	C	5	Window Sash	Wood	Brown	Fair	6.64	LBP
24	Mrs.Oliver's Cabin	N/A	E. Bedroom	A	5	Window Sash	Wood	Stain	Fair	ND	NEG
25	Mrs.Oliver's Cabin	N/A	W. Bedroom	N/A	6	Ceiling	Wood	White	Fair	ND	NEG
26	Mrs.Oliver's Cabin	N/A	Bathroom	N/A	6	Ceiling	Wood	Stain	Fair	0.01	LCP
27	Mrs.Oliver's Cabin	N/A	E. Bedroom	N/A	6	Ceiling	Wood	White	Fair	ND	NEG
28	Mrs.Oliver's Cabin	N/A	Bathroom	B	7	Baseboard	Wood	Stain	Fair	0.09	LCP

TABLE 2D
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Mrs. Oliver's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
29	Mrs.Oliver's Cabin	N/A	Exterior	A	8	Siding	Wood	Stain	Fair	0.02	LCP
30	Mrs.Oliver's Cabin	N/A	Exterior	B	8	Siding	Wood	Stain	Fair	0.01	LCP
31	Mrs.Oliver's Cabin	N/A	Exterior	C	8	Siding	Wood	Stain	Fair	ND	NEG
32	Mrs.Oliver's Cabin	N/A	Exterior	D	8	Siding	Wood	Stain	Fair	ND	NEG
33	Mrs.Oliver's Cabin	N/A	Exterior	A	9	Door	Wood	Brown	Poor	6.6	LBP
34	Mrs.Oliver's Cabin	N/A	Exterior	A	10	Door Casing	Wood	Brown	Poor	6.92	LBP
35	Mrs.Oliver's Cabin	N/A	Exterior	A	11	Window Casing	Wood	Brown	Poor	6.08	LBP
36	Mrs.Oliver's Cabin	N/A	Exterior	B	11	Window Casing	Wood	Brown	Poor	5.68	LBP
37	Mrs.Oliver's Cabin	N/A	Exterior	C	11	Window Casing	Wood	Brown	Poor	6.14	LBP
38	Mrs.Oliver's Cabin	N/A	Exterior	A	12	Window Sash	Wood	Brown	Poor	5.64	LBP
39	Mrs.Oliver's Cabin	N/A	Exterior	B	12	Window Sash	Wood	Brown	Poor	5.66	LBP
40	Mrs.Oliver's Cabin	N/A	Exterior	C	12	Window Sash	Wood	Brown	Poor	6.43	LBP
41	Mrs.Oliver's Cabin	N/A	Exterior	A	13	Soffit	Wood	Stain	Fair	ND	NEG
42	Mrs.Oliver's Cabin	N/A	Exterior	B	13	Soffit	Wood	Stain	Fair	ND	NEG
43	Mrs.Oliver's Cabin	N/A	Exterior	C	13	Soffit	Wood	Stain	Fair	ND	NEG
44	Mrs.Oliver's Cabin	N/A	Exterior	D	13	Soffit	Wood	Stain	Fair	ND	NEG
45	Mrs.Oliver's Cabin	N/A	Exterior	A	14	Crawlspace Hatch	Wood	Brown	Poor	3.3	LBP

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2E
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Middle Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	Middle Cabin	N/A	Exterior	A	1	Siding	Wood	Stain	Fair	0.01	LCP
2	Middle Cabin	N/A	Exterior	B	1	Siding	Wood	Stain	Fair	0.01	LCP
3	Middle Cabin	N/A	Exterior	C	1	Siding	Wood	Stain	Fair	ND	NEG
4	Middle Cabin	N/A	Exterior	D	1	Siding	Wood	Stain	Fair	ND	NEG
5	Middle Cabin	N/A	Exterior	A	2	Door	Wood	Brown	Poor	5.65	LBP
6	Middle Cabin	N/A	Exterior	A	3	Door Casing	Wood	Brown	Poor	7.26	LBP
7	Middle Cabin	N/A	Exterior	A	4	Window Casing	Wood	Brown	Poor	7.38	LBP
8	Middle Cabin	N/A	Exterior	C	4	Window Casing	Wood	Brown	Poor	6.82	LBP
9	Middle Cabin	N/A	Exterior	A	5	Window Sash	Wood	Brown	Poor	6.81	LBP
10	Middle Cabin	N/A	Exterior	C	5	Window Sash	Wood	Brown	Poor	6.05	LBP
11	Middle Cabin	N/A	Exterior	A	6	Soffit	Wood	Stain	Fair	ND	NEG
12	Middle Cabin	N/A	Exterior	B	6	Soffit	Wood	Stain	Fair	ND	NEG
13	Middle Cabin	N/A	Exterior	C	6	Soffit	Wood	Stain	Fair	ND	NEG
14	Middle Cabin	N/A	Exterior	D	6	Soffit	Wood	Stain	Fair	ND	NEG
15	Middle Cabin	N/A	W. Bedroom	A	7	Wall	Wood	Stain	Fair	ND	NEG
16	Middle Cabin	N/A	W. Bedroom	B	7	Wall	Wood	Stain	Fair	ND	NEG
17	Middle Cabin	N/A	W. Bedroom	C	7	Wall	Wood	Stain	Fair	ND	NEG
18	Middle Cabin	N/A	W. Bedroom	D	7	Wall	Wood	Stain	Fair	ND	NEG
19	Middle Cabin	N/A	Bathroom	A	7	Wall	Wood	Stain	Fair	ND	NEG
20	Middle Cabin	N/A	Bathroom	B	7	Wall	Wood	Stain	Fair	0.02	LCP
21	Middle Cabin	N/A	Bathroom	C	7	Wall	Wood	Stain	Fair	0.02	LCP
22	Middle Cabin	N/A	Bathroom	D	7	Wall	Wood	Stain	Fair	0.02	LCP
23	Middle Cabin	N/A	E. Bedroom	A	7	Wall	Wood	Stain	Fair	ND	NEG
24	Middle Cabin	N/A	E. Bedroom	B	7	Wall	Wood	Stain	Fair	ND	NEG
25	Middle Cabin	N/A	E. Bedroom	C	7	Wall	Wood	Stain	Fair	ND	NEG
26	Middle Cabin	N/A	E. Bedroom	D	7	Wall	Wood	Stain	Fair	ND	NEG
27	Middle Cabin	N/A	W. Bedroom	A	8	Door	Wood	Stain	Fair	ND	NEG
28	Middle Cabin	N/A	Bathroom	A	8	Door	Wood	Stain	Fair	ND	NEG

TABLE 2E
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Middle Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
29	Middle Cabin	N/A	E. Bedroom	A	8	Door	Wood	Stain	Fair	0.02	LCP
30	Middle Cabin	N/A	W. Bedroom	A	9	Door Casing	Wood	Stain	Fair	ND	NEG
31	Middle Cabin	N/A	Bathroom	A	9	Door Casing	Wood	Stain	Fair	ND	NEG
32	Middle Cabin	N/A	E. Bedroom	A	9	Door Casing	Wood	Stain	Fair	0.03	LCP
33	Middle Cabin	N/A	W. Bedroom	N/A	10	Ceiling	Wood	White	Fair	ND	NEG
34	Middle Cabin	N/A	Bathroom	N/A	10	Ceiling	Wood	Stain	Fair	0.01	LCP
35	Middle Cabin	N/A	E. Bedroom	N/A	10	Ceiling	Wood	White	Fair	ND	NEG
36	Middle Cabin	N/A	W. Bedroom	A	11	Window Casing	Wood	Stain	Fair	ND	NEG
37	Middle Cabin	N/A	Bathroom	C	11	Window Casing	Wood	Stain	Fair	ND	NEG
38	Middle Cabin	N/A	E. Bedroom	C	11	Window Casing	Wood	Stain	Fair	0.02	LCP
39	Middle Cabin	N/A	W. Bedroom	A	12	Window Sash	Wood	Brown	Poor	5.93	LBP
40	Middle Cabin	N/A	Bathroom	C	12	Window Sash	Wood	Stain	Fair	0.01	LCP
41	Middle Cabin	N/A	E. Bedroom	C	12	Window Sash	Wood	Brown	Poor	6.65	LBP

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2F
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - River Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	Lazy F Ranch	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.04	LBP
2	Lazy F Ranch	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.04	LBP
3	Lazy F Ranch	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1	LBP
4	Lazy F Ranch	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.03	LBP
5	River Cabin	N/A	Porch	A	1	Porch Rail	Wood	Brown	Poor	0.01	LCP
6	River Cabin	N/A	Porch	N/A	2	Porch Floor	Wood	Brown	Poor	0.03	LCP
7	River Cabin	N/A	Porch	A	3	Proch Column	Wood	Brown	Poor	0.04	LCP
8	River Cabin	N/A	Porch	A	4	Steps	Wood	Brown	Poor	ND	NEG
9	River Cabin	N/A	Porch	A	5	Porch Beam	Wood	Brown	Poor	0.02	LCP
10	River Cabin	N/A	Exterior	C	6	Window Casing	Wood	Brown	Poor	0.01	LCP
11	River Cabin	N/A	Exterior	C	7	Window Sill	Wood	Brown	Poor	0.01	LCP
12	River Cabin	N/A	Exterior	C	8	Door Casing	Wood	Brown	Poor	0.01	LCP
13	River Cabin	N/A	Exterior	C	9	Door	Wood	Stain	Poor	0	NEG
14	River Cabin	N/A	Exterior	A	6	Window Casing	Wood	Brown	Poor	ND	NEG
15	River Cabin	N/A	Exterior	D	6	Window Casing	Wood	Brown	Poor	0.03	LCP
16	River Cabin	N/A	Exterior	A	7	Window Sill	Wood	Brown	Poor	0.01	LCP
17	River Cabin	N/A	Exterior	D	7	Window Sill	Wood	Brown	Poor	ND	NEG
18	River Cabin	N/A	Exterior	D	10	Propain Tank	Metal	White	Poor	0.43	LCP
19	River Cabin	N/A	Exterior	A	11	Siding	Wood	Stain	Poor	0.03	LCP
20	River Cabin	N/A	Exterior	B	11	Siding	Wood	Stain	Poor	0.01	LCP
21	River Cabin	N/A	Exterior	C	11	Siding	Wood	Stain	Poor	0.02	LCP
22	River Cabin	N/A	Exterior	D	11	Siding	Wood	Stain	Poor	0.03	LCP
23	River Cabin	N/A	Exterior	A	12	Soffit	Wood	Stain	Poor	0	NEG
24	River Cabin	N/A	Exterior	B	12	Soffit	Wood	Stain	Poor	ND	NEG
25	River Cabin	N/A	Exterior	C	12	Soffit	Wood	Stain	Poor	ND	NEG
26	River Cabin	N/A	Exterior	D	12	Soffit	Wood	Stain	Poor	ND	NEG
27	River Cabin	N/A	Bedroom	A	13	Wall	Wood	Stain	Fair	ND	NEG
28	River Cabin	N/A	Bedroom	B	13	Wall	Wood	Stain	Fair	ND	NEG

TABLE 2F
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - River Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
29	River Cabin	N/A	Bedroom	C	13	Wall	Wood	Stain	Fair	ND	NEG
30	River Cabin	N/A	Bedroom	D	13	Wall	Wood	Stain	Fair	ND	NEG
31	River Cabin	N/A	Closet	A	13	Wall	Wood	Stain	Fair	ND	NEG
32	River Cabin	N/A	Closet	B	13	Wall	Wood	Stain	Fair	ND	NEG
33	River Cabin	N/A	Closet	C	13	Wall	Wood	Stain	Fair	ND	NEG
34	River Cabin	N/A	Closet	D	13	Wall	Wood	Stain	Fair	0	NEG
35	River Cabin	N/A	Bathroom	A	14	Wall	Drywall	White	Fair	0.01	LCP
36	River Cabin	N/A	Bathroom	B	14	Wall	Drywall	White	Fair	0.01	LCP
37	River Cabin	N/A	Bathroom	C	14	Wall	Drywall	White	Fair	ND	NEG
38	River Cabin	N/A	Bathroom	D	14	Wall	Drywall	White	Fair	0.02	LCP
39	River Cabin	N/A	Bedroom	N/A	15	Ceiling	Wood	Stain	Fair	ND	NEG
40	River Cabin	N/A	Closet	N/A	15	Ceiling	Wood	Stain	Fair	ND	NEG
41	River Cabin	N/A	Bathroom	N/A	15	Ceiling	Wood	Stain	Fair	ND	NEG
42	River Cabin	N/A	Bedroom	A	16	Door	Wood	Stain	Fair	0.01	LCP
43	River Cabin	N/A	Bathroom	B	16	Door	Wood	Stain	Fair	ND	NEG
44	River Cabin	N/A	Bedroom	N/A	17	Floor	Wood	Stain	Fair	ND	NEG
45	River Cabin	N/A	Bathroom	N/A	17	Floor	Wood	Stain	Fair	ND	NEG
46	River Cabin	N/A	Bedroom	A	18	Window Casing	Wood	Stain	Fair	ND	NEG
47	River Cabin	N/A	Bathroom	D	18	Window Casing	Wood	Stain	Fair	ND	NEG
48	River Cabin	N/A	Bedroom	A	19	Window Sill	Wood	Stain	Fair	0.01	LCP
49	River Cabin	N/A	Bathroom	D	19	Window Sill	Wood	Stain	Fair	ND	NEG

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2G
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Nurse's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	Nurse's Cabin	N/A	S. Bedroom	A	1	Wall	Wood	Stain	Fair	ND	NEG
2	Nurse's Cabin	N/A	S. Bedroom	B	1	Wall	Wood	Stain	Fair	0	NEG
3	Nurse's Cabin	N/A	S. Bedroom	C	1	Wall	Wood	Stain	Fair	ND	NEG
4	Nurse's Cabin	N/A	S. Bedroom	D	1	Wall	Wood	Stain	Fair	ND	NEG
5	Nurse's Cabin	N/A	Hallway	A	2	Wall	Drywall	White	Fair	ND	NEG
6	Nurse's Cabin	N/A	Hallway	B	2	Wall	Drywall	White	Fair	ND	NEG
7	Nurse's Cabin	N/A	Hallway	C	2	Wall	Drywall	White	Fair	ND	NEG
8	Nurse's Cabin	N/A	Hallway	D	2	Wall	Drywall	White	Fair	ND	NEG
9	Nurse's Cabin	N/A	Bathroom	A	2	Wall	Drywall	White	Fair	0.02	LCP
10	Nurse's Cabin	N/A	Bathroom	B	2	Wall	Drywall	White	Fair	ND	NEG
11	Nurse's Cabin	N/A	Bathroom	C	2	Wall	Drywall	White	Fair	0.02	LCP
12	Nurse's Cabin	N/A	Bathroom	D	2	Wall	Drywall	White	Fair	0.02	LCP
13	Nurse's Cabin	N/A	Storage Room	A	2	Wall	Drywall	White	Fair	ND	NEG
14	Nurse's Cabin	N/A	Storage Room	B	2	Wall	Drywall	White	Fair	ND	NEG
15	Nurse's Cabin	N/A	Storage Room	C	2	Wall	Drywall	White	Fair	ND	NEG
16	Nurse's Cabin	N/A	Storage Room	D	2	Wall	Drywall	White	Fair	ND	NEG
17	Nurse's Cabin	N/A	N. Bedroom	A	1	Wall	Wood	Stain	Fair	ND	NEG
18	Nurse's Cabin	N/A	N. Bedroom	B	1	Wall	Wood	Stain	Fair	ND	NEG
19	Nurse's Cabin	N/A	N. Bedroom	C	1	Wall	Wood	Stain	Fair	ND	NEG
20	Nurse's Cabin	N/A	N. Bedroom	D	1	Wall	Wood	Stain	Fair	ND	NEG
21	Nurse's Cabin	N/A	S. Bedroom	B	3	Door	Wood	Stain	Fair	ND	NEG
22	Nurse's Cabin	N/A	Hallway	C	3	Door	Wood	Stain	Fair	ND	NEG

TABLE 2G
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Nurse's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
23	Nurse's Cabin	N/A	Bathroom	B	3	Door	Wood	Stain	Fair	0.01	LCP
24	Nurse's Cabin	N/A	N. Bedroom	B	3	Door	Wood	Stain	Fair	ND	NEG
25	Nurse's Cabin	N/A	S. Bedroom	B	4	Door Casing	Wood	Stain	Fair	ND	NEG
26	Nurse's Cabin	N/A	Hallway	A	4	Door Casing	Wood	Stain	Fair	0.03	LCP
27	Nurse's Cabin	N/A	Bathroom	B	4	Door Casing	Wood	Stain	Fair	0.01	LCP
28	Nurse's Cabin	N/A	Storage Room	A	4	Door Casing	Wood	Stain	Fair	0.01	LCP
29	Nurse's Cabin	N/A	N. Bedroom	B	4	Door Casing	Wood	Stain	Fair	ND	NEG
30	Nurse's Cabin	N/A	S. Bedroom	C	5	Window Casing	Wood	Stain	Fair	ND	NEG
31	Nurse's Cabin	N/A	Hallway	B	5	Window Casing	Wood	Stain	Fair	0.01	LCP
32	Nurse's Cabin	N/A	Bathroom	D	5	Window Casing	Wood	Stain	Fair	ND	NEG
33	Nurse's Cabin	N/A	Storage Room	D	5	Window Casing	Wood	Stain	Fair	0.02	LCP
34	Nurse's Cabin	N/A	N. Bedroom	A	5	Window Casing	Wood	Stain	Fair	0.02	LCP
35	Nurse's Cabin	N/A	S. Bedroom	C	6	Window Sill	Wood	Stain	Fair	ND	NEG
36	Nurse's Cabin	N/A	Bathroom	D	6	Window Sill	Wood	Stain	Fair	ND	NEG
37	Nurse's Cabin	N/A	Storage Room	D	6	Window Sill	Wood	Stain	Fair	0.03	LCP
38	Nurse's Cabin	N/A	N. Bedroom	A	6	Window Sill	Wood	Stain	Fair	0.04	LCP
39	Nurse's Cabin	N/A	S. Bedroom	N/A	7	Ceiling	Wood	White	Fair	ND	NEG
40	Nurse's Cabin	N/A	Hallway	N/A	8	Ceiling	Drywall	White	Fair	ND	NEG
41	Nurse's Cabin	N/A	Bathroom	N/A	8	Ceiling	Drywall	White	Fair	0.04	LCP
42	Nurse's Cabin	N/A	Storage Room	N/A	8	Ceiling	Drywall	White	Fair	ND	NEG
43	Nurse's Cabin	N/A	N. Bedroom	N/A	7	Ceiling	Wood	White	Fair	ND	NEG
44	Nurse's Cabin	N/A	S. Bedroom	N/A	9	Floor	Wood	Stain	Fair	0.68	LCP

TABLE 2G
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Nurse's Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
45	Nurse's Cabin	N/A	N. Bedroom	N/A	9	Floor	Wood	Brown	Fair	0.12	LCP
46	Nurse's Cabin	N/A	Exterior	A	10	Siding	Wood	Stain	Fair	0.03	LCP
47	Nurse's Cabin	N/A	Exterior	B	10	Siding	Wood	Stain	Fair	0.02	LCP
48	Nurse's Cabin	N/A	Exterior	C	10	Siding	Wood	Stain	Fair	0.01	LCP
49	Nurse's Cabin	N/A	Exterior	D	10	Siding	Wood	Stain	Fair	0.01	LCP
50	Nurse's Cabin	N/A	Exterior	B	11	Door	Wood	Stain	Fair	0.01	LCP
51	Nurse's Cabin	N/A	Exterior	B	12	Door Casing	Wood	Brown	Fair	5.34	LBP
52	Nurse's Cabin	N/A	Exterior	A	13	Soffit	Wood	Stain	Fair	ND	NEG
53	Nurse's Cabin	N/A	Exterior	B	13	Soffit	Wood	Stain	Fair	ND	NEG
54	Nurse's Cabin	N/A	Exterior	C	13	Soffit	Wood	Stain	Fair	ND	NEG
55	Nurse's Cabin	N/A	Exterior	D	13	Soffit	Wood	Stain	Fair	ND	NEG
56	Nurse's Cabin	N/A	Exterior	A	14	Window Casing	Wood	Stain	Fair	0.85	LCP
57	Nurse's Cabin	N/A	Exterior	C	14	Window Casing	Wood	Stain	Fair	ND	NEG
58	Nurse's Cabin	N/A	Exterior	D	14	Window Casing	Wood	Brown	Fair	7.17	LBP

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2H
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Main Lodge
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	Main Lodge	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.02	LBP
2	Main Lodge	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.01	LBP
3	Main Lodge	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	0.97	LBP
4	Main Lodge	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1	LBP
5	Main Lodge	N/A	Pantry	A	1	Wall	Wood	Stain	Poor	ND	NEG
6	Main Lodge	N/A	Pantry	B	1	Wall	Wood	Stain	Poor	ND	NEG
7	Main Lodge	N/A	Pantry	C	1	Wall	Wood	Stain	Poor	ND	NEG
8	Main Lodge	N/A	Pantry	D	1	Wall	Wood	Stain	Poor	0.01	LCP
9	Main Lodge	N/A	Kitchen	A	2	Wall	Drywall	White	Poor	ND	NEG
10	Main Lodge	N/A	Kitchen	B	2	Wall	Drywall	White	Poor	0.02	LCP
11	Main Lodge	N/A	Kitchen	C	2	Wall	Drywall	White	Poor	0.02	LCP
12	Main Lodge	N/A	Kitchen	D	2	Wall	Drywall	White	Poor	0.02	LCP
13	Main Lodge	N/A	Dining	A	1	Wall	Wood	Stain	Poor	ND	NEG
14	Main Lodge	N/A	Dining	B	1	Wall	Wood	Stain	Poor	ND	NEG
15	Main Lodge	N/A	Dining	C	1	Wall	Wood	Stain	Poor	ND	NEG
16	Main Lodge	N/A	Dining	D	1	Wall	Wood	Stain	Poor	ND	NEG
17	Main Lodge	N/A	Living	A	1	Wall	Wood	Stain	Poor	ND	NEG
18	Main Lodge	N/A	Living	B	1	Wall	Wood	Stain	Poor	ND	NEG
19	Main Lodge	N/A	Living	C	1	Wall	Wood	Stain	Poor	ND	NEG
20	Main Lodge	N/A	Living	D	1	Wall	Wood	Stain	Poor	ND	NEG
21	Main Lodge	N/A	Great Room	A	1	Wall	Wood	Stain	Poor	0	NEG
22	Main Lodge	N/A	Great Room	B	1	Wall	Wood	Stain	Poor	ND	NEG
23	Main Lodge	N/A	Great Room	C	1	Wall	Wood	Stain	Poor	ND	NEG
24	Main Lodge	N/A	Great Room	D	1	Wall	Wood	Stain	Poor	ND	NEG
25	Main Lodge	N/A	E. Bedroom	A	1	Wall	Wood	Stain	Poor	ND	NEG
26	Main Lodge	N/A	E. Bedroom	B	1	Wall	Wood	Stain	Poor	ND	NEG
27	Main Lodge	N/A	E. Bedroom	C	1	Wall	Wood	Stain	Poor	ND	NEG
28	Main Lodge	N/A	E. Bedroom	D	1	Wall	Wood	Stain	Poor	ND	NEG

TABLE 2H
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Main Lodge
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
29	Main Lodge	N/A	Bathroom	A	1	Wall	Wood	White	Poor	ND	NEG
30	Main Lodge	N/A	Bathroom	B	1	Wall	Wood	Stain	Poor	ND	NEG
31	Main Lodge	N/A	Bathroom	C	1	Wall	Wood	Stain	Poor	ND	NEG
32	Main Lodge	N/A	Bathroom	D	1	Wall	Wood	White	Poor	ND	NEG
33	Main Lodge	N/A	W. Bedroom	A	1	Wall	Wood	Stain	Poor	ND	NEG
34	Main Lodge	N/A	W. Bedroom	B	1	Wall	Wood	Stain	Poor	ND	NEG
35	Main Lodge	N/A	W. Bedroom	C	1	Wall	Wood	Stain	Poor	ND	NEG
36	Main Lodge	N/A	W. Bedroom	D	1	Wall	Wood	Stain	Poor	ND	NEG
37	Main Lodge	N/A	Pantry	B	3	Door	Wood	Stain	Poor	0.02	LCP
38	Main Lodge	N/A	Kitchen	A	3	Door	Wood	Stain	Poor	ND	NEG
39	Main Lodge	N/A	Dining	C	3	Door	Wood	Stain	Poor	0.04	LCP
40	Main Lodge	N/A	Living	C	3	Door	Wood	Stain	Poor	0.01	LCP
41	Main Lodge	N/A	Great Room	D	3	Door	Wood	Stain	Poor	ND	NEG
42	Main Lodge	N/A	E. Bedroom	A	3	Door	Wood	Stain	Poor	ND	NEG
43	Main Lodge	N/A	Bathroom	C	3	Door	Wood	Stain	Poor	ND	NEG
44	Main Lodge	N/A	W. Bedroom	C	3	Door	Wood	Stain	Poor	ND	NEG
45	Main Lodge	N/A	Pantry	B	4	Door Casing	Wood	Stain	Poor	0.03	LCP
46	Main Lodge	N/A	Kitchen	A	4	Door Casing	Wood	Stain	Poor	ND	NEG
47	Main Lodge	N/A	Dining	C	4	Door Casing	Wood	Stain	Poor	0.03	LCP
48	Main Lodge	N/A	Living	C	4	Door Casing	Wood	Stain	Poor	ND	NEG
49	Main Lodge	N/A	Great Room	D	4	Door Casing	Wood	Stain	Poor	ND	NEG
50	Main Lodge	N/A	E. Bedroom	A	4	Door Casing	Wood	Stain	Poor	ND	NEG
51	Main Lodge	N/A	Bathroom	C	4	Door Casing	Wood	Stain	Poor	0	NEG
52	Main Lodge	N/A	W. Bedroom	C	4	Door Casing	Wood	Stain	Poor	ND	NEG
53	Main Lodge	N/A	Kitchen	D	5	Window Casing	Wood	Stain	Poor	0.02	LCP
54	Main Lodge	N/A	Dining	B	5	Window Casing	Wood	Stain	Poor	ND	NEG
55	Main Lodge	N/A	Living	D	5	Window Casing	Wood	Stain	Poor	ND	NEG
56	Main Lodge	N/A	Great Room	D	5	Window Casing	Wood	Stain	Poor	ND	NEG

TABLE 2H
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Main Lodge
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
57	Main Lodge	N/A	E. Bedroom	B	5	Window Casing	Wood	Stain	Poor	ND	NEG
58	Main Lodge	N/A	W. Bedroom	D	5	Window Casing	Wood	Stain	Poor	ND	NEG
59	Main Lodge	N/A	Kitchen	D	6	Window Sash	Wood	Brown	Poor	5.16	LBP
60	Main Lodge	N/A	Dining	B	6	Window Sash	Wood	Stain	Poor	ND	NEG
61	Main Lodge	N/A	Living	D	6	Window Sash	Wood	Brown	Poor	3.24	LBP
62	Main Lodge	N/A	Great Room	D	6	Window Sash	Wood	Brown	Poor	3.94	LBP
63	Main Lodge	N/A	E. Bedroom	B	6	Window Sash	Wood	Brown	Poor	5.5	LBP
64	Main Lodge	N/A	W. Bedroom	D	6	Window Sash	Wood	Brown	Poor	5.89	LBP
65	Main Lodge	N/A	Dining	N/A	7	Floor	Wood	Brown	Poor	0.02	LCP
66	Main Lodge	N/A	Living	N/A	7	Floor	Wood	Brown	Poor	ND	NEG
67	Main Lodge	N/A	Great Room	N/A	7	Floor	Wood	Brown	Poor	0	NEG
68	Main Lodge	N/A	E. Bedroom	N/A	7	Floor	Wood	Brown	Poor	0.04	LCP
69	Main Lodge	N/A	Bathroom	N/A	7	Floor	Wood	Gray	Poor	0.18	LCP
70	Main Lodge	N/A	W. Bedroom	N/A	7	Floor	Wood	Brown	Poor	0.01	LCP
71	Main Lodge	N/A	Pantry	N/A	8	Ceiling	Wood	Stain	Poor	ND	NEG
72	Main Lodge	N/A	Kitchen	N/A	9	Ceiling	Drywall	White	Poor	0.02	LCP
73	Main Lodge	N/A	Dining	N/A	8	Ceiling	Wood	Stain	Poor	ND	NEG
74	Main Lodge	N/A	Living	N/A	8	Ceiling	Wood	Stain	Poor	ND	NEG
75	Main Lodge	N/A	Great Room	N/A	8	Ceiling	Wood	Stain	Poor	ND	NEG
76	Main Lodge	N/A	E. Bedroom	N/A	8	Ceiling	Wood	Stain	Poor	ND	NEG
77	Main Lodge	N/A	Bathroom	N/A	8	Ceiling	Wood	Stain	Poor	ND	NEG
78	Main Lodge	N/A	W. Bedroom	N/A	8	Ceiling	Wood	Stain	Poor	ND	NEG
79	Main Lodge	N/A	Kitchen	A	10	Cabinet	Wood	Stain	Poor	ND	NEG
80	Main Lodge	N/A	Kitchen	B	10	Cabinet	Wood	Stain	Poor	0.03	LCP
81	Main Lodge	N/A	Kitchen	C	10	Cabinet	Wood	Stain	Poor	0.01	LCP
82	Main Lodge	N/A	Exterior	0	11	Siding	Wood	Stain	Poor	0.01	LCP
83	Main Lodge	N/A	Exterior	0	11	Siding	Wood	Stain	Poor	ND	NEG
84	Main Lodge	N/A	Exterior	0	11	Siding	Wood	Stain	Poor	0.01	LCP

TABLE 2H
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Main Lodge
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
85	Main Lodge	N/A	Exterior	0	11	Siding	Wood	Stain	Poor	0.01	LCP
86	Main Lodge	N/A	Exterior	0	12	Door	Wood	Brown	Poor	5.86	LBP
87	Main Lodge	N/A	Exterior	0	12	Door	Wood	Brown	Poor	0.32	LCP
88	Main Lodge	N/A	Exterior	0	12	Door	Wood	Brown	Poor	6.79	LBP
89	Main Lodge	N/A	Exterior	0	13	Door Casing	Wood	Brown	Poor	7.22	LBP
90	Main Lodge	N/A	Exterior	0	13	Door Casing	Wood	Brown	Poor	5.3	LBP
91	Main Lodge	N/A	Exterior	0	13	Door Casing	Wood	Brown	Poor	5.43	LBP
92	Main Lodge	N/A	Exterior	0	14	Window Casing	Wood	Brown	Poor	5.98	LBP
93	Main Lodge	N/A	Exterior	0	14	Window Casing	Wood	Brown	Poor	6.73	LBP
94	Main Lodge	N/A	Exterior	0	15	Window Sash	Wood	Brown	Poor	8.8	LBP
95	Main Lodge	N/A	Exterior	0	15	Window Sash	Wood	Brown	Poor	7.81	LBP
96	Main Lodge	N/A	Exterior	0	16	Soffit	Wood	Brown	Poor	0.01	LCP
97	Main Lodge	N/A	Exterior	0	16	Soffit	Wood	Brown	Poor	0.01	LCP
98	Main Lodge	N/A	Exterior	0	16	Soffit	Wood	Brown	Poor	0.01	LCP
99	Main Lodge	N/A	Exterior	0	16	Soffit	Wood	Brown	Poor	0.01	LCP
100	Main Lodge	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.04	LBP
101	Main Lodge	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.01	LBP
102	Main Lodge	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1	LBP

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2I
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Ice House
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	Ice House	N/A	Exterior	A	1	Siding	Wood	Stain	Fair	ND	NEG
2	Ice House	N/A	Exterior	B	1	Siding	Wood	Stain	Fair	ND	NEG
3	Ice House	N/A	Exterior	C	1	Siding	Wood	Stain	Fair	0.01	LCP
4	Ice House	N/A	Exterior	D	1	Siding	Wood	Stain	Fair	0.01	LCP
5	Ice House	N/A	Exterior	A	2	Door	Wood	Stain	Fair	0	NEG
6	Ice House	N/A	Exterior	A	3	Door Casing	Wood	Stain	Fair	ND	NEG
7	Ice House	N/A	Exterior	A	4	Soffit	Wood	Stain	Fair	ND	NEG
8	Ice House	N/A	Exterior	B	4	Soffit	Wood	Stain	Fair	ND	NEG
9	Ice House	N/A	Exterior	C	4	Soffit	Wood	Stain	Fair	ND	NEG
10	Ice House	N/A	Exterior	D	4	Soffit	Wood	Stain	Fair	ND	NEG
11	Ice House	N/A	Storage	A	5	Wall	Wood	Stain	Fair	ND	NEG
12	Ice House	N/A	Storage	B	5	Wall	Wood	Stain	Fair	ND	NEG
13	Ice House	N/A	Storage	C	5	Wall	Wood	Stain	Fair	ND	NEG
14	Ice House	N/A	Storage	D	5	Wall	Wood	Stain	Fair	ND	NEG
15	Ice House	N/A	Storage	N/A	6	Ceiling	Wood	Stain	Fair	ND	NEG
16	Ice House	N/A	Storage	A	7	Door	Wood	Stain	Fair	ND	NEG
17	Ice House	N/A	Walk-in Freezer	B	8	Cooler	Metal	Gray	Fair	ND	NEG
18	Ice House	N/A	Walk-in Freezer	D	8	Cooler	Metal	Gray	Fair	ND	NEG
19	Ice House	N/A	Walk-in Freezer	D	9	Cooler Door	Metal	Gray	Fair	ND	NEG
20	Ice House	N/A	Freezer	D	9	Cooler Door	Metal	Silver	Fair	0.19	LCP
21	Ice House	N/A	Freezer	A	8	Cooler	Metal	Silver	Fair	0.2	LCP
22	Ice House	N/A	Freezer	D	8	Cooler	Metal	Silver	Fair	0.1	LCP
23	Ice House	N/A	Exterior	D	10	Propane Tank	Metal	White	Fair	0.01	LCP

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2J
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - Mouse House
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	Mouse House	N/A	Exterior	A	1	Siding	Wood	Stain	Fair	ND	NEG
2	Mouse House	N/A	Exterior	B	1	Siding	Wood	Stain	Fair	ND	NEG
3	Mouse House	N/A	Exterior	C	1	Siding	Wood	Stain	Fair	ND	NEG
4	Mouse House	N/A	Exterior	D	1	Siding	Wood	Stain	Fair	ND	NEG
5	Mouse House	N/A	Exterior	A	2	Door	Wood	Stain	Fair	ND	NEG
6	Mouse House	N/A	Exterior	A	3	Door Casing	Wood	Stain	Fair	0	NEG
7	Mouse House	N/A	Exterior	A	4	Soffit	Wood	Stain	Fair	ND	NEG
8	Mouse House	N/A	Exterior	B	4	Soffit	Wood	Stain	Fair	ND	NEG
9	Mouse House	N/A	Exterior	C	4	Soffit	Wood	Stain	Fair	ND	NEG
10	Mouse House	N/A	Exterior	D	4	Soffit	Wood	Stain	Fair	ND	NEG

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2K
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - New Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	New Cabin	N/A	Exterior	A	1	Siding	Wood	Stain	Fair	ND	NEG
2	New Cabin	N/A	Exterior	B	1	Siding	Wood	Stain	Fair	ND	NEG
3	New Cabin	N/A	Exterior	C	1	Siding	Wood	Stain	Fair	ND	NEG
4	New Cabin	N/A	Exterior	D	1	Siding	Wood	Stain	Fair	ND	NEG
5	New Cabin	N/A	Exterior	A	2	Door	Wood	Stain	Fair	ND	NEG
6	New Cabin	N/A	Exterior	A	3	Door Casing	Wood	Stain	Fair	ND	NEG
7	New Cabin	N/A	Exterior	A	4	Window Casing	Wood	Stain	Fair	ND	NEG
8	New Cabin	N/A	Exterior	B	4	Window Casing	Wood	Stain	Fair	ND	NEG
9	New Cabin	N/A	Exterior	D	4	Window Casing	Wood	Stain	Fair	ND	NEG
10	New Cabin	N/A	Exterior	A	5	Window Sash	Wood	Stain	Fair	ND	NEG
11	New Cabin	N/A	Exterior	B	5	Window Sash	Wood	Stain	Fair	ND	NEG
12	New Cabin	N/A	Exterior	D	5	Window Sash	Wood	Stain	Fair	0	NEG
13	New Cabin	N/A	Exterior	A	6	Soffit	Wood	Stain	Fair	ND	NEG
14	New Cabin	N/A	Exterior	B	6	Soffit	Wood	Stain	Fair	0	NEG
15	New Cabin	N/A	Exterior	C	6	Soffit	Wood	Stain	Fair	ND	NEG
16	New Cabin	N/A	Exterior	D	6	Soffit	Wood	Stain	Fair	ND	NEG
17	New Cabin	N/A	Bedroom	A	7	Wall	Wood	Stain	Poor	0.01	LCP
18	New Cabin	N/A	Bedroom	B	7	Wall	Wood	Stain	Poor	0.01	LCP
19	New Cabin	N/A	Bedroom	C	7	Wall	Wood	Stain	Poor	0.01	LCP
20	New Cabin	N/A	Bedroom	D	7	Wall	Wood	Stain	Poor	0.01	LCP
21	New Cabin	N/A	Closet	A	7	Wall	Wood	Stain	Poor	0.01	LCP
22	New Cabin	N/A	Closet	B	7	Wall	Wood	Stain	Poor	0.01	LCP
23	New Cabin	N/A	Closet	C	7	Wall	Wood	Stain	Poor	0.01	LCP
24	New Cabin	N/A	Closet	D	7	Wall	Wood	Stain	Poor	ND	NEG
25	New Cabin	N/A	Bathroom	A	7	Wall	Wood	Stain	Poor	0.01	LCP
26	New Cabin	N/A	Bathroom	B	7	Wall	Wood	Stain	Poor	ND	NEG
27	New Cabin	N/A	Bathroom	C	7	Wall	Wood	Stain	Poor	0.01	LCP
28	New Cabin	N/A	Bathroom	D	7	Wall	Wood	Stain	Poor	0.01	LCP

TABLE 2K
RESULTS OF XRF INSTRUMENT PAINT TESTING

4 Lazy F Ranch - New Cabin
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
29	New Cabin	N/A	Bedroom	N/A	8	Ceiling	Wood	Stain	Poor	0.02	LCP
30	New Cabin	N/A	Closet	N/A	8	Ceiling	Wood	Stain	Poor	0.02	LCP
31	New Cabin	N/A	Bathroom	N/A	8	Ceiling	Wood	Stain	Poor	ND	NEG
32	New Cabin	N/A	Bedroom	A	9	Door	Wood	Stain	Poor	ND	NEG
33	New Cabin	N/A	Closet	D	9	Door	Wood	Stain	Poor	0.02	LCP
34	New Cabin	N/A	Bathroom	D	9	Door	Wood	Stain	Poor	ND	NEG
35	New Cabin	N/A	Bedroom	A	10	Door Casing	Wood	Stain	Poor	0.02	LCP
36	New Cabin	N/A	Closet	D	10	Door Casing	Wood	Stain	Poor	0.02	LCP
37	New Cabin	N/A	Bathroom	D	10	Door Casing	Wood	Stain	Poor	ND	NEG
38	New Cabin	N/A	Bedroom	A	11	Window Casing	Wood	Stain	Poor	0.01	LCP
39	New Cabin	N/A	Bathroom	B	11	Window Casing	Wood	Stain	Poor	ND	NEG
40	New Cabin	N/A	Bedroom	D	12	Window Sash	Wood	Stain	Poor	0.01	LCP
41	New Cabin	N/A	Bathroom	B	12	Window Sash	Wood	Stain	Poor	0.01	LCP
42	New Cabin	N/A	Bedroom	N/A	13	Floor	Wood	Stain	Poor	ND	NEG
43	New Cabin	N/A	Closet	N/A	13	Floor	Wood	Stain	Poor	ND	NEG
44	New Cabin	N/A	Bathroom	N/A	13	Floor	Wood	Stain	Poor	ND	NEG

* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

TABLE 2L
RESULTS OF XRF INSTRUMENT PAINT TESTING

Lazt F Ranch - 3-Bay Garage
4 Lazy F Ranch Road
Moose, Wyoming

Read. No	Site	Floor	Room	Side*	Mat. No.	Component	Substrate	Color	Cond.	Lead Content (mg/cm ²)	Result
1	3-Bay Garage	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.01	LBP
2	3-Bay Garage	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.03	LBP
3	3-Bay Garage	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.04	LBP
4	3-Bay Garage	N/A	Interior	A	1	Wall	Wood	Stain	Poor	ND	NEG
5	3-Bay Garage	N/A	Interior	B	1	Wall	Wood	Stain	Poor	ND	NEG
6	3-Bay Garage	N/A	Interior	C	1	Wall	Wood	Stain	Poor	0.01	LCP
7	3-Bay Garage	N/A	Interior	D	1	Wall	Wood	Stain	Poor	ND	NEG
8	3-Bay Garage	N/A	Exterior	A	2	Siding	Wood	Stain	Poor	ND	NEG
9	3-Bay Garage	N/A	Exterior	B	2	Siding	Wood	Stain	Poor	0.01	LCP
10	3-Bay Garage	N/A	Exterior	C	2	Siding	Wood	Stain	Poor	ND	NEG
11	3-Bay Garage	N/A	Exterior	D	2	Siding	Wood	Stain	Poor	ND	NEG
12	3-Bay Garage	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.03	LBP
13	3-Bay Garage	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.03	LBP
14	3-Bay Garage	N/A	N/A	N/A	N/A	Calibration	N/A	N/A	N/A	1.04	LBP



* LBP = Lead-based paint - equal to or greater than 1.0 mg/cm² measured using XRF screening.

* LCP = Lead-containing paint - detectable lead less than 1.0 mg/cm² measured using XRF screening.

* NEG = No lead detected measured using XRF screening.

GENERAL NOTES

- 1. No lead-based painted components were identified in this building.



LBP LOCATION DRAWING
HARRY'S CABIN



DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg


PROJECT NAME: 4 LAZY F RANCH
4 LAZY F RANCH ROAD
LOCATION: MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

NOT TO SCALE

FIG. 1.0A: LBP LOCATION DRAWING
HARRY'S CABIN

GENERAL NOTES

- 1. No lead-based painted components were identified in this building.



LBP LOCATION DRAWING
GEORGE'S CABIN



NOT TO SCALE

FIG. 1.0B: LBP LOCATION DRAWING
GEORGE'S CABIN




DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg

PROJECT NAME: 4 LAZY F RANCH
LOCATION: 4 LAZY F RANCH ROAD
MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

KEY NOTES

- ① LBP on Exterior Window Components
- ② LBP on Exterior Door Components
- ③ LBP on Interior Window Sash



LBP LOCATION DRAWING
END CABIN



NOT TO SCALE

FIG. 1.0C: LBP LOCATION DRAWING
END CABIN





DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg

PROJECT NAME: 4 LAZY F RANCH
4 LAZY F RANCH ROAD
LOCATION: MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

KEY NOTES

- ① LBP on Exterior Window Components
- ② LBP on Exterior Door Components
- ③ LBP on Interior Window Sash
- ④ LBP on Crawlspace Hatch



LBP LOCATION DRAWING
MRS. OLIVER'S CABIN



DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg



PROJECT NAME: 4 LAZY F RANCH
LOCATION: 4 LAZY F RANCH ROAD
MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

NOT TO SCALE

FIG. 1.0D: LBP LOCATION DRAWING
MRS. OLIVER'S CABIN

KEY NOTES

- ① LBP on Exterior Window Components
- ② LBP on Exterior Door Components
- ③ LBP on Interior Window Sash



LBP LOCATION DRAWING
MIDDLE CABIN



DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg


PROJECT NAME: 4 LAZY F RANCH
LOCATION: 4 LAZY F RANCH ROAD
MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

NOT TO SCALE

FIG. 1.0E: LBP LOCATION DRAWING
MIDDLE CABIN

GENERAL NOTES

- 1. No lead-based painted components were identified in this building.



LBP LOCATION DRAWING
RIVER CABIN



NOT TO SCALE

FIG. 1.0F: LBP LOCATION DRAWING
RIVER CABIN





DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg

PROJECT NAME: 4 LAZY F RANCH
4 LAZY F RANCH ROAD
LOCATION: MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

KEY NOTES

- ① LBP on Exterior Window Components
- ② LBP on Exterior Door Components



LBP LOCATION DRAWING
NURSE'S CABIN



DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg



PROJECT NAME: 4 LAZY F RANCH
LOCATION: 4 LAZY F RANCH ROAD
MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

NOT TO SCALE

FIG. 1.0H: LBP LOCATION DRAWING
NURSE'S CABIN

KEY NOTES

- ① LBP on Exterior Window Components
- ② LBP on Exterior Door Components
- ③ LBP on Interior Window Components



LBP LOCATION DRAWING
MAIN LODGE



DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg


PROJECT NAME: 4 LAZY F RANCH
4 LAZY F RANCH ROAD
MOOSE, WYOMING
LOCATION: NIH PROJECT NUMBER: 999-5237

NOT TO SCALE

FIG. 1.0H: LBP LOCATION DRAWING
MAIN LODGE

GENERAL NOTES

- 1. No lead-based painted components were identified in this building.



LBP LOCATION DRAWING
ICE HOUSE



DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg



PROJECT NAME: 4 LAZY F RANCH
4 LAZY F RANCH ROAD
LOCATION: MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

NOT TO SCALE

FIG. 1.01: LBP LOCATION DRAWING
ICE HOUSE

GENERAL NOTES

- 1. No lead-based painted components were identified in this building.



LBP LOCATION DRAWING
MOUSE HOUSE



DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg


PROJECT NAME: 4 LAZY F RANCH
4 LAZY F RANCH ROAD
LOCATION: MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

NOT TO SCALE

FIG. 1.0J: LBP LOCATION DRAWING
MOUSE HOUSE

GENERAL NOTES

- 1. No lead-based painted components were identified in this building.



LBP LOCATION DRAWING
NEW CABIN



NOT TO SCALE

FIG. 1.0K: LBP LOCATION DRAWING
NEW CABIN





DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg

PROJECT NAME:
4 LAZY F RANCH
4 LAZY F RANCH ROAD
MOOSE, WYOMING
LOCATION:
NIH PROJECT NUMBER:
999-5237

GENERAL NOTES

- 1. No lead-based painted components were identified in this building.



LBP LOCATION DRAWING
3-BAY GARAGE



NOT TO SCALE

FIG. 1.0L: LBP LOCATION DRAWING
3-BAY GARAGE



DATE: JULY 2025
DRAWN BY: CH
CHK BY: MO
CAD FILE: 999-5237.dwg

PROJECT NAME: 4 LAZY F RANCH
4 LAZY F RANCH ROAD
LOCATION: MOOSE, WYOMING
NIH PROJECT NUMBER: 999-5237

United States Environmental Protection Agency

This is to certify that



Christopher A Hust

has fulfilled the requirements of the Toxic Substances Control Act (TSCA) Section 402, and has received certification to conduct lead-based paint activities pursuant to 40 CFR Part 745.226 as:

Inspector

In the Jurisdiction of:

All EPA Administered Lead-based Paint Activities Program States, Tribes and Territories

This certification is valid from the date of issuance and expires September 14, 2026

LBP-I-I248548-1

Certification #

August 31, 2023

Issued On



Adrienne Priselac, Manager, Toxics Office

Land Division

United States Environmental Protection Agency

This is to certify that

Northern Industrial Hygiene

has fulfilled the requirements of the Toxic Substances Control Act (TSCA) Section 402, and has received certification to conduct lead-based paint activities pursuant to 40 CFR Part 745.226

In the Jurisdiction of:

All EPA Administered Lead-based Paint Activities Program States, Tribes and Territories

This certification is valid from the date of issuance and expires April 15, 2024

LBP-2386-1

Certification #

April 01, 2021

Issued On



Michelle Price, Chief

Lead, Heavy Metals, and Inorganics Branch

Certificate of Training

Chris Hust

of Northern Industrial Hygiene Inc has completed the SciAps instrument operator training for the X550 Pb Analyzer, provided by Tom Lambert

SciAps

**Instrument Operator Training
X550 Pb Analyzer**

I confirm that the above named individual has received the training listed on this certificate.



Tom Lambert
Name

December 11, 2023
Date

Certified Trainer
Title

I certify that I have received the stated training and understand the content presented.

Chris Hust
Name

December 11, 2023
Date





North Dakota Department of
Environmental Quality Certificate
of
Lead-Based Paint Abatement

No. 424

This is to certify that Christopher A.W. Hunt has met the
requirements of Chapter 33.1-15-24 of the North Dakota Air Pollution Control
Rules for certification in the following lead-based paint abatement discipline(s):

Supervisor

Worker

☒ Inspector

Risk Assessor

Project Designer

Exp: 1/25/2026

LEP Control Program

Performance Characteristic Sheet

EFFECTIVE DATE: February 1, 2022

MANUFACTURER AND MODEL:

Make: **SciAps**
 Models: **Model X-550**
 X-Ray Source: **Rhodium (Rh) or Gold (Au) Anode**

FIELD OPERATION GUIDANCE

ACTION LEVEL SETTING:

1.0 mg/cm²

OPERATING PARAMETERS:

Timed mode: fixed 10-second reading.

Quick mode: variable-time reading (approximately 2-6 seconds).

XRF CALIBRATION CHECK LIMITS:

0.8 to 1.2 mg/cm ² (inclusive) on NIST SRM 2579 (1.02 mg/cm ²)/NIST SRM 2573, or equivalent
--

SUBSTRATE CORRECTION:

Not applicable

INCONCLUSIVE RANGE OR THRESHOLD:

Au Anode (quick) READING DESCRIPTION	SUBSTRATE	THRESHOLD (mg/cm²)
Results not corrected for substrate bias on any substrate	Brick	1.0
	Concrete	1.0
	Drywall	1.0
	Metal	1.0
	Plaster	1.0
	Wood	1.0
Rh Anode (Timed or Quick), Au Anode (Timed) READING DESCRIPTION	SUBSTRATE	THRESHOLD (mg/cm²)
Results not corrected for substrate bias on any substrate	Brick	0.9
	Concrete	0.9
	Drywall	0.9
	Metal	0.9
	Plaster	0.9
	Wood	0.9

BACKGROUND INFORMATION

EVALUATION DATA SOURCE AND DATE:

This sheet is supplemental information to be used in conjunction with Chapter 7 of the HUD *Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing*, 2012 Edition ("HUD Guidelines"). Performance parameters shown on this sheet are calculated using test results on building components in the HUD archive. Testing was conducted on 146 test samples in February 2022, with two separate instruments of each Anode type, operated in both Timed and Quick modes.

OPERATING PARAMETERS

Performance parameters shown in this sheet are applicable only when properly operating the instrument using the manufacturer's instructions and procedures described in Chapter 7 of the HUD Guidelines.

XRF CALIBRATION CHECK:

The calibration of the XRF instrument should be checked using the paint film nearest 1.0 mg/cm² in the NIST Standard Reference Material (SRM) used (e.g., for NIST SRM 2579, use the 1.02 mg/cm² film; for NIST SRM 2579a, use film 2573 (1.04 mg/cm²).

If the average (rounded to 1 decimal place) of three readings is outside the acceptable calibration check range, follow the manufacturer's instructions to bring the instrument into control before XRF testing proceeds.

EVALUATING THE QUALITY OF XRF TESTING:

Randomly select ten testing combinations for retesting from each house or from two randomly selected units in multifamily housing.

Conduct XRF re-testing at the ten testing combinations selected for retesting.

Determine if the XRF testing in the units or house passed or failed the test by applying the steps below. Compute the Retest Tolerance Limit by the following steps:

Determine XRF results for the original and retest XRF readings. In single-family and multifamily housing, a result is defined as a single reading. Therefore, there will be ten original and ten retest XRF results for each house or for the two selected units.

Calculate the average of the original XRF result and the retest XRF result for each testing combination.

Square the average for each testing combination.

Add the ten squared averages together. Call this quantity C.

Multiply the number C by 0.0072. Call this quantity D.

Add the number 0.032 to D. Call this quantity E.

Take the square root of E. Call this quantity F.

Multiply F by 1.645. The result is the Retest Tolerance Limit.

Compute the average of all ten original XRF readings.

Compute the average of all ten re-test XRF readings.

Find the absolute difference of the two averages.

If the difference is less than the Retest Tolerance Limit, the inspection has passed the retest. If the difference of the overall averages equals or exceeds the Retest Tolerance Limit, this

procedure should be repeated with ten new testing combinations. If the difference of the overall averages is equal to or greater than the Retest Tolerance Limit a second time, then the inspection should be considered deficient.

Use of this procedure is estimated to produce a spurious result approximately 1% of the time. That is, results of this procedure will call for further examination when no examination is warranted in approximately 1 out of 100 dwelling units tested.

TESTING TIMES:

The reading time in Archive tests was 10 seconds in Timed mode and from 2-6 seconds in Quick mode, for both the Rh Anode and Au Anode.

CLASSIFICATION OF RESULTS:

XRF results for the Au Anode in Quick mode are classified as **positive** if they are **greater than or equal** to 1.0 mg/cm² and **negative** if they are **less than** 1.0 mg/cm². XRF results for the Au Anode in Timed mode and for the Rh Anode in Timed or Quick mode are classified as **positive** if they are **greater than or equal** to 0.9 mg/cm² and **negative** if they are **less than** 0.9 mg/cm².

DOCUMENTATION:

A report titled *Methodology for XRF Performance Characteristic Sheets* (EPA 747-R-95-008) provides an explanation of the statistical methodology used to develop Performance Characteristic Sheets at the Federal standard (Action Level) of 1.0 mg/cm² and provides empirical results from using the recommended inconclusive ranges or thresholds for specific XRF instruments. The report may be downloaded at <http://www2.epa.gov/lead/methodology-xrf-performance-characteristic-sheets-epa-747-r-95-008-september-1997>.