

Public Questions & Answers

Event Information

Number: 26100
Title: COLLECTION SYSTEM CONSTRUCTION SERVICES FY 26-27
Type: Invitation for Bid
Issue Date: 9/1/2026
Question Deadline: 9/22/2026 05:00 PM (PT)
Response Deadline: 10/8/2026 02:00 PM (PT)
Notes: SCOPE OF WORK: The Work may consist of all or part of the following: cured-in-place pipe (CIPP) lining; manhole repair and coating; removal and replacement of pipelines, pipe segments, and manholes; repairing manhole frames, covers, collars, and adjusting grade rings; construction of new gravity sewer pipelines and manholes, abandoning pipelines and manholes; lateral connections; notifying 811 One Call center; coordinating with utility owners, homeowners and other contractors; obtaining permits; bypass pumping; planning, setting, and removal of barricades, cutting asphalt; compacting backfill; surface restoration; and all other appurtenant work required.

The Site of Work is located at various areas throughout Las Vegas Valley.

ESTIMATED COST: The Engineer's estimate is in the \$7,900,000.00 to \$9,200,000.00 range.

Published Questions

Question: For Bid Items 5-10, 16-24, is it correct to assume that "provide" includes installation?

Answer: Surface features such as asphalt pavement, driveways, sidewalks, curb & gutter, and valley gutters are covered in separate bid items for billing. Other surface features are listed in paragraph 1.10.D of Section 01 20 05.

Asked: 9/22/2026 09:26 AM (PT)

Question: For Bid Item #3 "Install 4"-6" PVC Lateral, (0' to 6") (After Main Connection), what is the assumption for surface conditions? Or is Surface make good to be billed separately?

Answer: In Section 01 20 05, paragraph B for articles 1.14, 1.15, 1.16, 1.19, 1.20, and 1.21 identifies work includes installation or construction.

Asked: 9/22/2026 09:20 AM (PT)

Question: Will alternate lining technologies be considered? Specifically, structural, styrene free PVC Fold & Form liners meeting ASTM F 1871-24. Thermoform liner is a factory manufactured PVC Liner solution available up to 48" in diameter. Thermoform exceeds the material properties of standard polyester CIPP liners. CIPP liners are manufactured on site and involve a wet-out process and "cure" to determine their final material properties. Thermoform Liner is factory manufactured and material properties are determined at the point of extrusion. Thermoform is extruded with a specific wall thickness based on design calculations to ensure the required wall thickness is met. I have attached our Technical Guide for your review.

https://drive.google.com/file/d/1bUrF3lEYy1_oB71OUuT5bbrYPLpDWaMo/view?usp=drive_link

Answer: PVC Fold and Form liners can be submitted in accordance with Section 01 25 00 Or Equal Procedures if it complies with Section 33 01 36 Cured-In-Place (CIPP) and Machine Spiral Wound (MSW) PVC Rehabilitation requirements.

Asked: 9/15/2026 07:56 AM (PT)

Question: There are no plan sheets showing the locations of work included in the bid documents. Please make available, thank you

Answer: Drawings are unavailable in the Bid Documents. Scopes of work will be developed as needed once the project has notice to proceed.

Asked: 9/4/2026 08:23 AM (PT)