

Hurricane Ridge Rockfall, Hurricane Ridge Rockfall Mitigation MP 9.4

**Olympic National Park
Clallam County, Washington**

The primary objective of the project is to construct a rockfall mitigation system.

Project Location: This project is located approximately 11 Miles S of Port Angeles, WA.

Estimated Price Range between \$2,000,000 and \$5,000,000

Tentative Solicitation Date: Winter of 2026/ 2027

Tentative Fixed Completion Date: Fall 2027

**DESCRIPTION OF WORK in US CUSTOMARY UNITS
USING FP-24 SPECS**

	One Schedule Sch Name A
DIVISION 150 – Project Requirements	
152 Construction Survey & Staking (yes/no)	Yes
153 Contractor Quality Control and Assurance (yes/no)	Yes
154 Contractor Sampling & Testing (yes/no)	Yes
155 Schedules for Construction Contracts (<i>construction schedules</i>) (yes/no)	Yes
157 Soil Erosion & Sediment Control (<i>erosion control devices</i>)	
158 Watering for Dust Control	LPSM
DIVISION 200 – Earthwork	
201 Clearing & Grubbing	0.3 ACRE

	One Schedule Sch Name A
203 Removal of Structures & Obstructions (<i>relocate concrete barrier</i>)	125 LNFT
204 Excavation & Embankment	720 CUYD
DIVISION 250 – Slope Reinforcement and Retaining Walls	
257 Contactor-Designed Retaining Walls (contractor completed designs)	LPSM
259 Soil Nail Retaining Walls	1260 SQFT
265 Roadside Rockfall Protection, Fence	102 LNFT
269 Temporary Roadside Rockfall Protection, Fence	LPSM
DIVISION 300 – Aggregate and Base Courses	
302 Roadway Aggregate Method 1	18 CUYD
DIVISION 600 – Incidental Construction	
602 Culverts	240 LNFT
602 End Section	1 EACH
604 Inlets	1 EACH
617 Crash Cushion	2 EACH
618 Concrete Barriers	210 LNFT
622 Rental Equipment (yes/no)	Yes
623 General Labor (yes/no)	Yes
633 Sign System	25 SQFT
635 Temporary Traffic Control	LPSM
635 Temporary Traffic Control (Flagger)	1200 HOUR